

Listed Building Consent to replace 8 no. windows (3no. to the front and 5no. to the rear) with wooden sash windows, and repairs to window frames, to replace rear ground floor and kitchen casement windows with traditional sliding sash windows, and to replace the front door with a new hardwood painted door

12 Church Street Croston Leyland PR26 9HA

Schedule of works

Ground floor windows

WG01 – Existing window to be removed and replaced with hardwood fixed light to match existing

WG02 – Window to receive new hardwood timber sashes. Existing box frame to remain.

WG03 – Existing timber casement window replaced with 2No hardwood timber boxed framed sliding sash windows.

WG04 – Existing casement window replaced with 1No hardwood timber boxed framed sliding sash window.

WG05 – Existing casement window removed and replaced with hardwood casement fixed window to match existing.

First floor windows

WF01 - Window to receive new hardwood timber sashes. Existing box frame to remain.

WF02 – Existing window to be replaced with hardwood timber boxed framed sliding sash window to match existing.

WF03 - Existing window to be replaced with hardwood timber boxed framed sliding sash window to match existing.

Ground floor doors

DG01 – Existing hardwood timber door replaced with new hardwood timber door to match existing.



Fig 1 - WG01, DG01, WG02, WF01



Fig 2 – WG03, WG04, WF02, WF03



Fig 3 – WG03

