



# LOVAT

Brazilian Grey-Green

High quality grey-green slate, with a flat surface and pleasing grey shade variations. Can be relied upon to create an attractive and long lasting roof or floor. Has virtually no unstable minerals such as pyrites, graphite, carbon and un-oxidised irons and will withstand the most severe weather conditions. Unaffected by sunlight, ultraviolet light and even acid rain.

Slatescape recommend the use of hook fixing for our Brazilian ranges.

<b>SS03F</b>	<b>FIRST</b>	<b>5-7mm</b>	
Sizes (cm):	<b>40 x 20</b>	<b>40 x 30</b>	
	<b>50 x 25</b>	<b>50 x 30</b>	
	<b>50 x 37.5</b>	<b>50 x 45</b>	
	<b>60 x 30</b>	<b>60 x 45</b>	

<b>SS03H</b>	<b>HEAVY</b>	<b>7-9mm</b>	
Sizes (cm):	<b>40 x 20</b>	<b>40 x 30</b>	
	<b>50 x 25</b>	<b>50 x 37.5</b>	
	<b>60 x 30</b>		

### Technical Specification

European Standard: **EN 12326-1**

### Test Results

SO2 Exposure Test: **Complies S1**

Thermal Cycle Test: **Complies T1**

Water Absorption: **Complies W1**

Contents of Carbonate: **Complies <2%**

**Call us on 01254 685 175**

Email: [sales@slatescape.co.uk](mailto:sales@slatescape.co.uk)

Website: [www.slatescape.co.uk](http://www.slatescape.co.uk)

#seriousaboutslate #designthenation