



### Product Information

Ibstock Code:	0055
Type:	Stock
Facing Description:	Sandcreased
Dry Brick Weight (kg):	2.1kg
Pack Quantity:	430
Packaging (standard):	Banded (plastic) & Stretchwrapped
Factory:	Leicester

### Technical Specification (to BS EN 771-1)

Brick Dimensions (L x W x H mm):	215x102x65
Size Tolerances Mean & Range:	T2 R1
Configuration:	Single Frog
Voids (%):	8-13
Compressive Strength (N/mm <sup>2</sup> ):	20
Active Soluble Salts:	S2
Water Absorption (% weight):	19
Durability:	F2
Gross Dry Density (Sound Insulation) (Kg/m <sup>3</sup> ):	1530
Equivalent Thermal Conductivity "K" value 5% Exposed:	Refer to Ibstock
Initial Rate of Absorption (Suction Rate) (Kg/m <sup>2</sup> /min):	Refer to Ibstock
EAN:	5036335032749