


London Road

SUDS MANAGEMENT	COMMENTS	Potential for flow rate control	Volume reduction	Maintenance requirement	Space requirement	Collection mechanism
1. Rainwater harvesting	Rainwater from roof runoff collected for re-use	L	M	H	L	P
2. Water Butts	Rainwater from roof runoff collected for re-use	L	L	L	L	P
3. Living roofs	Vegetated roofs that reduce runoff volume and rate	M	L	M	L	S
4. Bio-retention	Shallow vegetated areas to retain and treat runoff	L	L	M	M	S
5. Permeable pavements	Surfaces that infiltrate through surface. Retains pollutants	H	H	M	L	S
6. Tanked storage systems	Oversized pipes or cellular storage	H	L	L	M	P
7. Trees	Trees within soil-filled treepits used to collect, store and treat runoff	L	L	L	L	P
8. Lawn and plants	New planting in amenity space for the site	M	M	M	H	S

KEY:

- L - Low
- M - Medium
- H - High
- P - Point
- S - Surface



LesleyCotton
architect
The Hive @ The Old Music Hall
106-108 Cowley Road
Oxford OX4 1JE
01865 403121