

ID No	Common Name	Biological Name	B55837 Category	Age Assessment	DBH	Height	Crown North	Crown East	Crown South	Crown West	RPA	1st Branch	Vigour	Amenity Value	Notes
T1	Cypress	Cupressus sp	B	M	40	10.6	3	2.5	2.5	2.1	4.8	n/a	G	M	A mature tree of moderate amenity value with some growth potential. Tree is in an innappropriate postion and is impacted by the care parking extension. It is proposed to remove this tree and replace with RT1 in a more appropriate position either to the front or the rear of the property.
T2	Laburnum	Laburnum angyroides	U	SM	140	6.5	2	2	1.1	1.1	n/a	N2	P	L	A very poor specimen largely moribund. To be removed.
T3	Lime	Tillia sp	A	SM	37/23	8.3	4	3	4	4	5.2	W2	G	M	A semi mature Lime with good potential. It is propose to retain this tree. The RPA has been dawn as assymetric due to the hard landscape (driveway) and proximity to the property and the tree is to be directly protected during works.
T4	Ash	Fraxinus excelsior	A	M	37/26/29/36	12.6	6	6.5	8	6.5	5	S4	G	H	A major tree of high amenity value. Not impacted by development apart from possible plant access in area defined as RAZ with appropriate ground protection measures.
T5	Maple	Acer sp	A	M	40	11.5	5.7	2.1	5.2	6.6	4.8	W2	G	H	A major tree of high amenity value. Not impacted by development apart from possible plant access in area defined as RAZ with appropriate ground protection measures.
T6	Holly	Ilex aquifolium	B	M	25/13/13/8	8.2	3.7	3.7	3.7	3.7	1.2	n/a	M	M	Tree is not impacted by development.
T7	Holly	Ilex aquifolium	B	M	22	7.6	3.2	3.2	3.2	3.2	2.6	n/a	M	L	Tre to be removed and replace with RT2 where appropriate on the site.