



28 April 2022
CG22/0043

Mr Joe Fairs
Operations Manager
Mill Construction
Woodheyes
Purdis Avenue
Ipswich IP3 8UE

Dear Mr Fairs,

RE: VEHICLE STRIKE, THE OLD SHIP INN, 2 VALLEY ROAD, CLACTON ON SEA, ESSEX CO15 4AR.

Introduction.

J.P Chick & Partners were commissioned to undertake an urgent structural inspection following a vehicle strike at the Old Ship Inn pub, Clacton on Sea. Sam Drake and Adrian Kurti of JP Chick & Partners attended the property on Monday 25th April 2022 for the inspection. Joe Fairs from Mills Construction was also present.

At the time of the inspection the building had been evacuated and hoardings erected around the damaged areas externally. The adjacent highway, B1027 Valley Road had been closed to prevent excessive vibration from road traffic causing further destabilisation of the structure. The vehicle responsible for the impact had been removed from site.

This document intends to itemise the structural damage to the building resulting from the vehicle strike, advise temporary propping to make the building safe in the short term and propose remedial works to reinstate the structure to a safe and stable condition.

Photographs are provided in Appendix A. Temporary works and propping details are provided in Appendix B. An indicative plan of the building is provided, with defect locations annotated, in Appendix C. Structural calculations are provided in Appendix D.

Description of the Building.

The building is a 17c Grade II listed pub, having rendered 9" brickwork external walls at ground floor and an oak frame at 1st floor and roof levels. The ground floor has a suspended timber structure with joists spanning in a front to back direction, the 1st floor is a framework of exposed oak beams, with oak joists spanning between beams as shown on the enclosed sketch. The pitched roof carcass was not inspected internally and is finished externally with plain clay tiles.

It is understood that the vehicle impacted the building on the north-east corner.

Structural Damage.

- The external wall panel at the point of impact has been destroyed between ground level and eaves level (Item 1), causing the timber lintel over the entrance door to lose its bearing.



- A horizontal crack in the brickwork continues around the front elevation (north) external wall approximately 1m above ground level (Item 2).
- 1st floor joists notched into the Oak beam over the bay window have been displaced and lost around 10mm of bearing (Item 3).
- An Oak beam supporting the 1st floor appeared excessively deflected. The plywood cladding around the beam was removed and the beam was found to have split through its full depth (Item 5). This beam also appears to have been subject to an historic woodworm infestation and has rotted. We do not consider that the split was caused by the vehicle impact, as historic dust and debris was found inside the split timber. This defect needs to be addressed and rectified as part of the remedial work, prior to this area being reopened to the public.
- A portion of the plasterboard ceiling appeared to be sagging excessively (Item 4).

Temporary propping.

A temporary propping scheme was discussed and agreed with the contractor on site. Sketches TW01 & TW02 were produced to illustrate the propping requirements and provided to the contractor to be implemented. These sketches have been reproduced in Appendix B of this report.

We consider that the closed Valley Road highway can be reopened once all of the props are in place as shown.

When the props are in place and the affected areas have been closed off to the public with the hoardings in place as shown in sketches TW01 & TW02, The Publican and their family can move back into the pub and reopen the bar.

During construction, whilst the oak beam is being replaced and the joists re-seated on the new structure, the rooms above this area should not be used.

Structural Remedial Works.

- Install props as indicated on enclosed sketches TW01 & TW02. Pack below ground floor joists at mid span as shown on Sketch TW01.
- Remove external render and internal finishes and carefully take down external wall brickwork for extents shown on Photographs 1 & 2 in Appendix C of this report. If any purlins or beams not identified in this report are found to be bearing on this wall, stop work and identify JP Chick & Partners immediately.
- Rebuild brickwork to reinstate the external wall. New brickwork is to be bonded into the existing. Brick units and bond are to match the existing arrangement. Any lintel and/or beam bearings must be rebuilt into the brickwork taking care to tightly pack any voids between the timber and brickwork with steel shims or well rammed dry pack. Any lintels damaged by the impact are to be identified to JP Chick & Partners for new lintel design.
- Pack voids between 1st floor joists and beam over the bay window with glued timber shims.
- Take down sagging ceiling finishes (Item 4). Inspect the exposed 1st floor joists and report any defects or excessive deflection in the joists themselves to JP Chick & Partners. If joists are in good condition replace the ceiling finishes with new plasterboard.



- Replace or repair the split Oak beam (Item 5) as shown on the enclosed sketch RW02, subject to approval by English Heritage.
We have provided two options for consideration.
 - A) Complete removal and replacement of the original beam with a new Oak section. We consider this the least intrusive option, as no shortening of the existing 1st floor joists will be necessary. The propping arrangement will need to be reconfigured to allow removal of the existing Oak beam. See Sketch RW02 in Appendix C.
 - B) The most desirable and unintrusive option would be to repair the existing oak beam, however given its current condition, we do not believe this is likely to be possible. A historic timber repair specialist could be commissioned to inspect the beam and advise whether it could be repaired. Contact JP Chick & Partners if required and we will advise a suitable specialist.

We did look into the option of augmenting the existing, failed oak beam with steelwork either side, however this proved impractical due to the existing arrangement of the building and the disruption it would cause.

- On completion of the works described above, internal and external finishes should be made good using materials to match existing.

I trust the above meets with your requirements. Should you require anything further please do not hesitate to contact the undersigned in the first instance.

Kind Regards



Sam Drake – Associate
For and on behalf of J.P Chick & Partners



APPENDIX A

Photographs



Impact damage to external wall. (Item 1).



Impact damage to external wall. (Item 1 & 2).



Impact damage to external wall. (Item 1 & 2).



Impact damage to external wall, internal view. (Item 1).



Partial loss of bearing to 1st floor joists over bay window. (Item 3).



Excessively deflected Oak beam. Historic woodworm. Rot. Split beam. (Item 5).



Split Oak beam. (Item 5).



Sagging ceiling finishes. (Item 4).



APPENDIX B

Temporary propping details

SKETCH SHEET

LOCATION: THE SHIP INN, CLACTON

JP Chick & Partners Ltd
Consulting Civil & Structural Engineers




Eng: SD Date: 4/22 Job No.: CG22/043 Sheet TW of 01

GROUND FLOOR (BAR) PLAN

1ST FLOOR STRUCTURE SHOWN OVER.

⊕ - ACREON PROP LOCATION (max 900mm dia)
REFER SHEET TW/02 FOR PROP DETAILS.

* CONFIRM DIRECTIONS
OF 1ST FLOOR
JOISTS



TIMBER PLATE ANCHORED TO ARCHWALL
FRONT
TIMBER PLATE ANCHORED TO FOOTPATH

ACREON PUSH-PIPE / LATHING PLIPPS
500mm MAX.

ENSURE PROP IS LOCATED BELOW TIMBER LINTEL.

HOARDING

SKETCH SHEET

LOCATION: THE SHIP INN, CLACTON



JP Chick & Partners Ltd
Consulting Civil & Structural Engineers



Eng: SD Date: 4/22 Job No.: 1022/043 Sheet T.W./02 of ...

PROP & SPREADER BEAM DETAILS

INTERNAL PROPS





APPENDIX C

Details of Structural Remedial Work.

SKETCH SHEET

LOCATION: THE SHIP INN, CLACTON


JP Chick & Partners Ltd
Consulting Civil & Structural Engineers



Eng: SD Date: 27/4/22 Job No.: CC22/43 Sheet RW/0.1 of 0.1

PART GROUND FLOOR (BAR) PLAN
1ST FLOOR STRUCTURE SHOWN OVER

DEFECT LOCATIONS



SKETCH SHEET

LOCATION: THE SHIP INN, CLACTON

JP Chick & Partners Ltd
Consulting Civil & Structural Engineers



Eng: SD Date: 27/04/22 Job No. KS22/043 Sheet R.W/02 of 02

OPTION A. REPLACE EXISTING BEAM.


TYPICAL SECTION

A-A

NEW 250mm x 280mm DP D50
oak beam to replace existing

1ST FLOOR.

Existing beam
notched into new
beam.



Existing Joists
notched into new
beam.


500mm
WORKING
SPACE.

2 AM

Handwritten notes and sketches at the bottom of the page, including a small structural diagram of a post and beam connection. The notes are partially illegible but appear to include details about the construction and materials.


PHOTOGRAPH 1

AREA OF EXTERNAL
WALL TO BE
DEMOLISHED &
REBUILT.



PHOTOGRAPH 1(2)

AREA OF EXTERNAL WALL
TO BE DEMOLISHED &
REBUILT





APPENDIX D

Structural Calculations

BEAM FAILURE.


Existing original Oak beam has failed.

∴ To design replacement.
in Steelwork:

UDL
(Outer)

1st floor Office @ $0.5 \times 2.6m/2$
Stud wall @ $0.5 \times 2.5 \times 2.6/2$
ROOF @ $1.2 \times 2.6m/2$
SNOW @ $0.6 \times 2.6m/2$

	(kN/m)	
	UK	QC
=	0.7	
=		3.3
=	1.1	
=		0.8
=	1.7	
<hr/>		
	3.5	4.1




$$M_x = 21 \text{ kNm}$$

$$M_v = 31.6 \text{ kNm}$$

PL @ MID SPAN
(inner)

1st FLOOR @ $0.5 \times 4.7m/2 \times 2.6m/2 = 1.5 \text{ kN}$
OFFICE @ $2.5 \times 4.7m/2 \times 2.6m/2 = 7.6 \text{ kN}$



$$M_x = 10.7 \text{ kNm}$$

$$M_v = 16.8 \text{ kNm}$$

THE SHIP INN, CLACTON

JP Chick & Partners Ltd
Consulting Civil & Structural Engineers



Designed

SD

Checked

Date

27/4/22

Job No.

622/043

CALCULATION SHEET

8 Atlantic Square Station Road Witham Essex CM8 2TL

Tel: (01376) 503020

www.chick.co.uk

chelmsford@chick.co.uk

SHEET NO.

C1

CONSIDER OAK BEAM - GRADE D50 - MIN 250x280mm

$$M_x = 21 + 10.7 = 31.7 \text{ kNm}$$

$$\sigma_{\text{cap}} = \frac{31.7 \times 10^6}{\left(\frac{250 \times 280^2}{6}\right)} = 9.7 \text{ N/mm}^2 < 16 \text{ N/mm}^2$$

\therefore BENDING OK.

- REFER FEEDS SHEETS FOR DEFLECTION CALC.


$$\delta = 12.5 \text{ mm} < 14 \text{ mm} \therefore \text{OK.}$$

CONSIDER GROUND FLOOR JOISTS UNDER PROPS.

$$\begin{aligned} \text{UDL THRO' PROPS (LESS SNOW LOAD)} &= 3.5 \text{ kN/m ok} \\ &= 4.1 - 0.8 = 3.3 \text{ kN/m ok} \end{aligned}$$

$$P \text{ (MID-SPAN)} = 1.5 \text{ kN ok}$$

$$\text{GF DL} = 0.5 \times 0.3 = 0.15 \text{ kN/m} + 3.5 = 3.65 \text{ kN/m ok}$$



$$M_x = 1.7 \text{ kNm}$$

50 x 180 C16 Joist

$$\sigma_{\text{cap}} = \frac{1.7 \times 10^6}{\left(\frac{50 \times 180^2}{6}\right)} = 6.3 > 5.3 \text{ N/mm}^2$$

$$\begin{aligned} \text{Allowable} &= 5.3 \times 1.06 \times 1.5 \\ &= 8.4 \text{ N/mm}^2 \\ &> 6.3 \therefore \text{OK} \end{aligned}$$

THE SHIP INN, CLACTON

JP Chick & Partners Ltd
Consulting Civil & Structural Engineers



Designed

SD

Checked

Date

27/4/22

Job No.

CL22/043

CALCULATION SHEET

8 Atlantic Square Station Road Witham Essex CM8 2TL

Tel: (01376) 503020
www.chick.co.uk


chelmsford@chick.co.uk

SHEET NO. C2

Project The Ship Inn, Clacton				Job no. CG22/043	
Calcs for Replacment Oak Beam				Start page no./Revision 4 C 3	
Calcs by SD	Calcs date 28/04/2022	Checked by	Checked date	Approved by	Approved date

TIMBER BEAM ANALYSIS & DESIGN TO BS5268-2:2002

TEDDS calculation version 1.7.02



Applied loading

Beam loads

Dead full UDL 3.500 kN/m
 Imposed full UDL 4.100 kN/m
 Dead point load 1.500 kN at 2350 mm
 Imposed point load 7.600 kN at 2350 mm

Load combinations

Load combination 1


Support A	Dead × 1.00 Imposed × 1.00
Span 1	Dead × 1.00 Imposed × 1.00
Support B	Dead × 1.00 Imposed × 1.00

Analysis results

Maximum moment	$M_{max} = 31.678$ kNm	$M_{min} = 0.000$ kNm
Design moment	$M = \max(\text{abs}(M_{max}), \text{abs}(M_{min})) = 31.678$ kNm	
Maximum shear	$F_{max} = 22.410$ kN	$F_{min} = -22.410$ kN
Design shear	$F = \max(\text{abs}(F_{max}), \text{abs}(F_{min})) = 22.410$ kN	

Project The Ship Inn, Clacton				Job no. CG22/043	
Calcs for Replacment Oak Beam				Start page no./Revision 5/CA	
Calcs by SD	Calcs date 28/04/2022	Checked by	Checked date	Approved by	Approved date

Total load on beam	$W_{tot} = 44.820 \text{ kN}$	
Reactions at support A	$R_{A_max} = 22.410 \text{ kN}$	$R_{A_min} = 22.410 \text{ kN}$
Unfactored dead load reaction at support A	$R_{A_Dead} = 8.975 \text{ kN}$	
Unfactored imposed load reaction at support A	$R_{A_Imposed} = 13.435 \text{ kN}$	
Reactions at support B	$R_{B_max} = 22.410 \text{ kN}$	$R_{B_min} = 22.410 \text{ kN}$
Unfactored dead load reaction at support B	$R_{B_Dead} = 8.975 \text{ kN}$	
Unfactored imposed load reaction at support B	$R_{B_Imposed} = 13.435 \text{ kN}$	



Timber section details

Breadth of sections	$b = 250 \text{ mm}$
Depth of sections	$h = 280 \text{ mm}$
Number of sections in member	$N = 1$
Overall breadth of member	$b_b = N \times b = 250 \text{ mm}$
Timber strength class	D50

Member details

Service class of timber	1
Load duration	Long term
Length of span	$L_{s1} = 4700 \text{ mm}$
Length of bearing	$L_b = 100 \text{ mm}$

Section properties

Cross sectional area of member	$A = N \times b \times h = 70000 \text{ mm}^2$
Section modulus	$Z_x = N \times b \times h^2 / 6 = 3266667 \text{ mm}^3$
	$Z_y = h \times (N \times b)^2 / 6 = 2916667 \text{ mm}^3$
Second moment of area	$I_x = N \times b \times h^3 / 12 = 457333333 \text{ mm}^4$
	$I_y = h \times (N \times b)^3 / 12 = 364583333 \text{ mm}^4$
Radius of gyration	$i_x = \sqrt{I_x / A} = 80.8 \text{ mm}$
	$i_y = \sqrt{I_y / A} = 72.2 \text{ mm}$

Modification factors

Duration of loading - Table 17	$K_3 = 1.00$
Bearing stress - Table 18	$K_4 = 1.00$
Total depth of member - cl.2.10.6	$K_7 = (300 \text{ mm} / h)^{0.11} = 1.01$
Load sharing - cl.2.9	$K_6 = 1.00$

Lateral support - cl.2.10.8

Ends held in position and members held in line, as by direct connection of sheathing, deck or joists	
Permissible depth-to-breadth ratio - Table 19	5.00
Actual depth-to-breadth ratio	$h / (N \times b) = 1.12$

PASS - Lateral support is adequate

Project		The Ship Inn, Clacton		Job no		CG22/043	
Calcs for		Replacement Oak Beam		Start page no /Revision		8 / CS	
Calcs by	Calcs date	Checked by	Checked date	Approved by	Approved date		
SD	28/04/2022						

Compression perpendicular to grain

Permissible bearing stress (no wane)

$$\sigma_{c_adm} = \sigma_{cp1} \times K_3 \times K_4 \times K_5 = 4.500 \text{ N/mm}^2$$

Applied bearing stress

$$\sigma_{c_a} = R_{A_max} / (N \times b \times L_b) = 0.896 \text{ N/mm}^2$$

$$\sigma_{c_a} / \sigma_{c_adm} = 0.199$$

PASS - Applied compressive stress is less than permissible compressive stress at bearing

Bending parallel to grain

Permissible bending stress

$$\sigma_{m_adm} = \sigma_m \times K_3 \times K_7 \times K_8 = 16.122 \text{ N/mm}^2$$

Applied bending stress

$$\sigma_{m_a} = M / Z_x = 9.697 \text{ N/mm}^2$$

$$\sigma_{m_a} / \sigma_{m_adm} = 0.602$$

PASS - Applied bending stress is less than permissible bending stress

Shear parallel to grain

Permissible shear stress

$$\tau_{adm} = \tau \times K_3 \times K_8 = 2.200 \text{ N/mm}^2$$

Applied shear stress

$$\tau_a = 3 \times F / (2 \times A) = 0.480 \text{ N/mm}^2$$

$$\tau_a / \tau_{adm} = 0.218$$

PASS - Applied shear stress is less than permissible shear stress

Deflection

Modulus of elasticity for deflection

$$E = E_{min} = 12600 \text{ N/mm}^2$$

Permissible deflection

$$\delta_{adm} = \min(0.551 \text{ in}, 0.003 \times L_{st}) = 13.995 \text{ mm}$$

Bending deflection

$$\delta_{b_s1} = 11.796 \text{ mm}$$

Shear deflection

$$\delta_{v_s1} = 0.690 \text{ mm}$$

Total deflection

$$\delta_a = \delta_{b_s1} + \delta_{v_s1} = 12.485 \text{ mm}$$

$$\delta_a / \delta_{adm} = 0.892$$

PASS - Total deflection is less than permissible deflection