

* Render spalling to lintel over upper flat entrance. Carefully remove boss render locally to expose lintel. Cut out lintel, replace with reinforced concrete, pack and re-render to match existing smooth band and roughcast

ALLAN PARK

