



Discreet low level roof vent installed into each roof face top and bottom

Timber batten attached to joist to allow minimum of 100mm rigid insulation to be placed between each rafter maintaining a 25mm air gap between existing battens and insulation

Breather membrane

Insulated plasterboard sheet 50mm

100mm rigid insulation

12.5mm Plasterboard and plaster finish

100mm rigid insulation

25mm cavity

PLANNING

**ANNA COULSON** - PAGECROFT WORKSHOP, HAYDON BRIDGE, NE47 6JX  
**ROOF INSULATION DETAIL** 1-10 / A3

DWG NO. P09 DATE: 08/02/2022 REVISION A

MYHUS

All information remains the property of the designer and may not be used for any purpose whatsoever, or reproduced through any medium without the permission of the designer. No responsibility is accepted for unauthorised used.  
 Do not scale off drawings. Work from figured dimensions only and verify on site.