

EXISTING REAR ELEVATION

scale 1:100

EXISTING SIDE ELEVATION

scale 1:100



PROPOSED REAR ELEVATION

scale 1:50



PROPOSED SIDE ELEVATION

scale 1:50

6. TIMBER PARTITIONS:- 100x50mm SC3 vertical softwood studs at 600mm c/c secured to 100x50mm SC3 head and sole plates. Noggins at 600mm intervals. 12.7mm Gyproc plasterboard and skim finish to both sides. Provide 25mm Isowool APR 1200 sound insulation to partition voids at bathrooms and around bedrooms to comply with E2 requirements for sound deadening. Floor joists to be doubled up when running parallel with and under timber partitions.

7. LINTELS:- Unless otherwise stated lintels to be Catnic combined steel to BS5977 (sizes as recommended by manufacturer). Provide min. 150mm end bearing where bearing is less than 150mm concrete padstones are to be provided (sizes to suit load and detail). All lintel backs and soffits to have min. half hour fire resistance and be insulated to prevent cold bridging where necessary. Where steel beams are used they are to be braced together 350mm from each bearing point and at mid span and set to concrete padstones each end as per Structural Engineer's drawings and details. Half hour fire protection to steelwork as above.

8. LATERAL RESTRAINT TO FLOOR AND ROOF:- All floors and roofs to be anchored by Bat or Catnic metal anchors (30 x5mm mild steel). Straps to be secured to timber elements and walls min. 1.0m long at max. 1.2m c/c (1.8m c/c in single storey construction).

9. PITCHED ROOF CONSTRUCTION:- Roof tiles to match existing in colour and style laid to gauge with 75mm headlaps on 50x25mm tanilised softwood battens secured with wire nails to BS5534. "TYVEK" breathable membrane laid to manufacturer's instructions (150mm laps), laid horizontally over specified rafters. Timber rafters as specified by Structural Engineer secured to a 100x50mm SC3 softwood wallplate strapped down to the external cavity walls. Provide timber collar-ties at high level for restraint, bolted to new rafters. Where insulation follows the rafters: 100mm Celotex GA4100 insulation set beween rafters with min 25mm ventilation gap maintained to underside of breathable membrane and fixed across face of rafters with a further 60mm Celotex PL4000 insulation and finished with 12.5mm plaster board (vapour check type) and skim finish. All to give a U-value of 0.15. Where insulation follows the ceiling: 100mm insulation laid between collar-ties with a further 2x 100mm insulation cross laid over to give total thickness of 300mm glass fibre quilt insulation. 12.7mm Gyproc Duplex plasterboard and skim finish ceiling. All to provide 'U' value of 0.15 or better. All valleys to be lined with code 4 lead work on treated softwood valley boards. Horizontal and vertical straps for lateral support as described above positioned at intervals not exceeding 1.8m.

10. FRAMES, CASINGS, SKIRTINGS, ARCHITRAVES :- Internal door linings shall be 100 x 38 with planted stops. Skirting boards shall be 100 x 19mm. chamfered. Architraves shall be 75x19 chamfered. All new internal doors to have min. undercut of 10mm above the fitted floor finish surface. Window frames with safety glazing to all doors, side panels, and all areas extending below 800mm from floor level and to be in accordance with BS 6206. New or replacement doors and windows to be UPVC and double or triple glazed, argon filled gaps and finished soft low 'E' coating to achieve U-value of 1.40 or window energy rate - Band B or better. New external doors with more than 60% of internal face glazed to have a U value of 1.40 or doorset energy rate - Band C or better, other external doors to have a U value of 1.40 or doorset energy rate - Band B or better. Installed either by Fensa registered installer or compliance via certificate from L.A. Building control (fee Payable). Max. area of windows, doors and roof lights should not exceed 25% of floor area of the extension.

11. ELECTRICAL INSTALLATION and PART P BUILDING REGULATIONS ELECTRICAL SAFETY:- Where electrical work is required to comply with Schedule 1 of the Building regulations it will either:

a. Be installed, by electrician who is registered as Part P approved by an authorised body (a completion certificate/certificate of compliance will need to be obtained from their authorised body (NICEIC, ELECSA, NAPIT etc.).

b. Any other electrician will require and Electrical Safety Building Notice application.

The proposed electrical installation, earthing and bonding to be installed to current IEE regulations & to comply with Part P requirements of the Building regulations. Mains operated, self contained and inter linked smoke alarms must be provided at each landing level and must conform to BS EN 14604 whilst heat alarms should be to BS 5446-2. The smoke alarms must conform to at least a Grade D2 Category LD3 in accordance with BS 5839-6. All units to have recharchable batteries in case of mains power loss. Fixed fitting taking only lamps having a luminous efficiency of 40 lumens per circuit watt shall be used at one per 25 m2 of floor area or three of four or 75% fittings which ever is the greater. Fixed external lighting shall be either lamp capacity not exceeding 150w per light fitting that switches off automatically or fittings taking only lamps of 40 lumens per circuit watt.

12. GAS INSTALLATION & HEATING:- The proposed gas installation shall be designed and installed by GASSAFE registered person and a relevant certificate provided to Building Control pre-completion. Extend existing central heating to new areas to client's instructions. Where new or replacement boilers are installed must be a condensing boiler and must have a SEDBUK rating of Class A or B and the condensate outlet must be taken to the foul drainage system. New radiators fitted with thermostatic type valves with pipework insulated to non heated locations.

13. NATURAL AND MECHANICAL VENTILATION:- Prior to completion details of commissioning and testing of mechanical systems for extracts to be deposited with building Control to show complaince with F1 (2).

a) Habitable room:
- Rapid ventilation - 1/20th of floor area - for a hinged or pivot window that opens 30° or more, or for sliding sash windows. 1/10th of floor area - for a hinged or pivot window that opens less than 30°.
- Background ventilation - 8000 mm²

b) Kitchen:
- Rapid ventilation - opening window
- Background ventilation - 8000 mm²
- Extract ventilation fan rates - 30 l/s adjacent to a hob or 60l/s elsewhere

c) Bathroom (with or without WC):
- Rapid ventilation - opening window
- Background ventilation - 5000 mm²
- Extract ventilation fan rates - 15 l/s

The extract fans to rooms like utility, WC and bathroom having no external opening window to be provided with a 15 minute overrun.

Location of mechanical ventilation devices in rooms:

a) Cooker hoods should be 650mm to 750mm above the hob surface (or follow manufacturer's instructions).

b) Mechanical extract fans should be placed as high as practicable and preferably less than 400mm below the ceiling. Refer to Appendix E Approved Document F for further guidance of installation of fans in dwellings.

THE CONTRACTOR SHALL ALLOW FOR MAKING GOOD OF ALL DISTURBED WORKS.

Other Notes, Alterations.

Notes:

All existing foundations, beams and/or lintels accepting additional load, are to be exposed, if necessary, for consideration by the Building Control Surveyor and upgraded if found necessary.



drawnplans.co.uk

Project:

Two Storey Rear Extension.

For:

Kelly Fergus
8 Harrison Terrace
Peterlee
County Durham
SR8 3HF

Scale:	Dwg. no:	Ref. no
As shown	Sheet 2	A0(
Drawn by:	Date Drawn:	
L.R.	29-August-2022	

For Drawings Tel: 0800 7836790

E-mail :- drawnplansco@aol.com