



Material Samples
for
Extension and Alterations
at
Park Cottage The Green Thorp Arch





Stone Sample

Stone Sample with a 3:1 lime mortar. 3 parts mixed graded sands and aggregates to 1 part lime that is no stronger than NHL 3.5. The mortar is colour matched to the stone using sands and aggregates. The mortar is slightly recessed from the face of the stone with a brushed back finish to expose the aggregates.





The Stables - Pan tile sample



The Stables - Pantile Sample

