



Plumbing For Less.co.uk



Follow @Plumbforless

Like < 35

BROWSE CATEGORIES

Bathrooms

Brassware and Bathroom Taps

Fixings

Guttering

Heating

Kitchen

Plumbing

Pumps and Macerators

Showers

Shower Enclosures

Shower Trays

Shower Rails And Curtains

Ventilation

Ducting

[Round Pipe Ducting 100mm](#)[Round Pipe Ducting 125mm](#)[Round Pipe Ducting 150mm](#)[Flat Channel Ducting 110mm X 54mm](#)[Flat Channel Ducting 204mm X 60mm](#)[Flat Channel Ducting 220mm X 90mm](#)[Flat Channel Ducting 225mm](#)[Flat Channel Ducting 300mm](#)[Flexible Hose System 100mm](#)[Flexible Hose System 125mm](#)[Flexible Hose System 150mm](#)[Flexible Hose Rectangular](#)[Grilles 100mm](#)

VENTILATION > DUCTING > GRILLES 100MM
> MANROSE EXTERNAL LOUVRED GRILLE W/ 100MM ROUND SPIGOT BLACK

MANROSE EXTERNAL LOUVRED GRILLE W/ 100MM ROUND SPIGOT BLACK



click image to enlarge

MANROSE
Quality Ventilation

Cat. No. 1151 BLACK - Manrose 140mm x 140mm External Square Louvred Wall Grille w/ Ø100mm (4") Round Spigot.

The Ø100mm round system is used for long duct runs where space is unrestricted and suitable for refurbishment or horizontal duct runs in roof and ceiling voids, and is designed specifically for applications requiring lower extraction rates such as in bathrooms, toilets, utility rooms and low power cooker hoods.

Louvred grilles can be used for air replacement, for extract purposes and as an external louvre (covering grille) fixed to outside of exterior wall to provide external termination and air intake.

- Fits [into](#) Ø100mm (4") Round Pipe Ducting to provide external termination and excellent airflow.
- For use with the Ø100mm (4") Round Pipe Ducting systems.
- Dimensions: 140mm x 140mm : Ø100mm (4").
- Connector type: Round spigot - male fitting - Ø100mm outer diameter.
- Maximum working temperature: 60° C.
- Free area: 6,500 mm².
- Suitable for use with gas appliances.
- Simple and easy fit - push-fit connections for quick installation.
- 4 pre-drilled fixing holes.
- Surface mounted.
- Lightweight.
- Material: Polystyrene, UV stable materials to reduce colour fade.
- Colour: Black.
- Flame retardant.
- Fixings not included.

Equivalent of Polypipe Ventilation/Domus (Easipipe 100) Product No. 4904BL.

For more information, please visit this products specification [webpage](#).

SHOP BY BRAND



Excellent

393 customers have written a review on Trustpilot

TRUSTPILOT