



- Fernhill Cottage boundary
- Existing hedge to south boundary
- New 600mm Wide Gravel maintenance path to tennis court and hedge
- New Evergreen hedge to perimeter of tennis court
- Proposed Tennis Court
- Tennis court to be constructed of pre-cast concrete kerb Edging to perimeter, 150mm of clean compacted stone sub-base, 40mm of open graded asphalt, 25mm of binder course and 6mm of open graded asphalt course. Tennis court surface will be a 18mm Multi use sports carpet with white sports court markings
- 1.5m Height V-mesh fencing to sides of tennis court with steel posts concreted into ground  
2m Height V-mesh fencing to front and rear of tennis court with steel posts concreted into ground

