



Fernhill Cottage boundary

Existing hedge to south boundary

New 600mm Wide Gravel maintenance path to tennis court and hedge

New Evergreen hedge to perimeter of tennis court

Proposed Tennis Court

Tennis court to be constructed of pre-cast concrete kerb Edging to perimeter, 150mm of clean compacted stone sub-base, 40mm of open graded asphalt, 25mm of binder course and 6mm of open graded asphalt course. Tennis court surface will be a 18mm Multi use sports carpet with white sports court markings

1.5m Height V-mesh fencing to sides of tennis court with steel posts concreted into ground
 2m Height V-mesh fencing to front and rear of tennis court with steel posts concreted into ground