

Palisade Panel - Rounded Tops

Jacksons Fencing



Palisade is a classic and enduring style of garden fencing that is also known as picket fencing and is available with pointed or rounded pale styles. Palisade panels are designed for use with our slotted Jakposts and manufactured from superior quality, planed finish Jakcure® treated softwood, guaranteed for 25 years and complete with stainless steel fixings that are used throughout for longer life. Also available in component form as a traditional system.

- All timber used throughout is superior quality Jakcure® treated softwood guaranteed for 25 years.
- All fixings are stainless steel.
- Designed for use with slotted Jakposts®.
- Classic traditional design and a planed finish.
- Please note, we supply in only natural Jakcure® treated finish.
- These panels are designed to be installed 50mm above the ground.
- Gravel boards are required where panels are in contact with the ground.

Specification

Panel Heights: 1m 1.2m

Panel Width: 1.83m

Pales: 22 x 75mm nominal section planed to finish at 19mm thick. Pale tops are machined with a rounded finish.

Each panel is backed by two 2ex 100 x 38mm rails fully planed.

Panels can be cut to a desired width on site. Always use Jakcure® End Grain Treatment on any cut timber.

Gates

Gates are Jakcure® treated softwood, right and left hand hanging (when viewed from the outside) as standard designed to match our Palisade Panel - Rounded Tops. Non-standard gates with custom width / heights are available as a special order and are also available as pairs (size restriction applies).

- Elegantly designed to match our Palisade Panel - Rounded Tops.
- Galvanised ring latch and adjustable hook and band hinges are included.
- All fixings and fittings are galvanised or stainless steel.
- All standard gates have no frame.

Standard Gate Heights: 0.95m, 1.15m & 1.75m.

Standard Gate Widths: 1m



View our website for Q40 specification documents, CAD drawings and products available to buy online.

A fully made to measure service is available. All Jacksons Fencing systems and gates may be designed and manufactured to suit site conditions.