

SCHEDULE OF WORKS WOODLANDS, BRUNDISH

To be read in conjunction with the Planning Statement and all Drawings

1.0 Windows

- 1.1 Existing Windows. Carefully remove existing windows
- 1.2 New Window Opening. Carefully remove plaster internally to area of new window opening and cut out wattle and daub panel. Remove render to area of new window opening.
- 1.3 New Windows. Supply and install new windows as drawn details, with slimlite glazing and black antique ironmongery.
- 1.4 Making Good. Make good render externally to wall around new window opening. Reinstate any broken laths in like for like timber and patch repair render using like for like render to adjacent walls.
- 1.4 Making Good. Make good plaster internally to window reveals around window openings using lime plaster.