



100 x 10mm ms welded ring with fixing sleeve to timber post and stainless steel fixing lugs Sign by others

250x 250 tapering to 150 x 150 timber post.

PUB SIGN.

Existing sign and planter removed and surface repaired. New pub sign constructed and installed.

High capacity electric car charging point supplied by others

Surface fixed galvanised conduit and junction box serving 2 No. adjustable external LED spot lights in black

Sign cast in mass concrete foundation 1000 x 1000 x 1000mm nom.

MH New main holes formed either in brick construction or UPVC proprietary units with standard heavy duty lids

FL. Existing lights to be removed and new feature lights TBC installed

A 12.6.22 Manhole 3 added for the Pump House.

Project: THE MALTINGS, WEYBOURNE, NORFOLK NR25 7SY			
Subject: HARDLANDSCAPING FINISHES TO FRONT.			
Scale: 1 : 100.	Date: May, 22	Project Ref: TM.	Drwg. No.: 227. Rev.: A
Architects: Big Brown Dog Limited		The Old Post Office, Brookside, Dalham, Suffolk CB8 8TG	
T: 01638 500234	F: 01638 500343	E: bigbrowndog@keme.co.uk	
Original size: A2			© BIG BROWN DOG LIMITED