

Trial Pit Photos

TP08

Manor Farm, Carburton

P21-00134



Photograph 23: TP08. Trial Pit.



Photograph 24: TP08. Topsoil Arisings.

Trial Pit Photos

TP08

Manor Farm, Carburton

P21-00134



Photograph 25: TP08. Arisings.



Met Consultancy Group Ltd
 Southgate House
 Pontefract Road
 Leeds
 LS10 1SW
 Email: admin@metconsultancygroup.com
 Phone: 0113 200 8900

Trial Pit Log

Trial Pit No
 TP09
 Sheet 1 of 1


Project Name: Manor Farm, Carburton

Project No.
 P21-00134

Co-ords: 461150.00 - 373374.00
 Level: 42.12

Date
 21/10/2021

Location: Manor Farm, Piper Lane, Carburton, S80 3BT



Scale
 1:25

Logged
 YK

Client: Wellbeck Estates Company Ltd

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description
	Depth	Type	Results				
				0.25	41.87		Grass overlying medium brown silty gravelly SAND (TOPSOIL) with frequent rootlets. Sand is fine. Gravel is subangular to rounded fine to coarse of mixed lithologies.
				0.50	41.62		Light brown gravelly SAND (SUBSOIL) with moderate cobble content. Sand is fine. Gravel is subangular to rounded fine to coarse of mixed lithologies. Cobbles are subrounded to rounded of mixed lithologies up to 100mm across.
				1.50	40.62		Orange gravelly SAND with high cobble content. Sand is fine to medium. Gravel is subrounded to rounded fine to coarse of mixed lithologies. Cobbles are subrounded to rounded fine to coarse of mixed lithologies up to 150mm across.
				3.00	39.12		Orange slightly gravelly SAND. Sand is fine to medium. Gravel is subrounded to rounded fine to coarse of mixed lithologies.
							End of Pit at 3.00m

Remarks: Ground observed to be generally loose during excavation by JCB, potentially denser from 2.6mbgl. Terminated due to reach of JCB.

Stability: Unstable Weather: Clear

Trial Pit Photos

TP09

Manor Farm, Carburton

P21-00134



Photograph 26: TP09 . Trial Pit.



Photograph 27: TP08. Topsoil Arisings.

Trial Pit Photos

TP09

Manor Farm, Carburton

P21-00134



Photograph 28: TP09. Arisings.



Met Consultancy Group Ltd
 Southgate House
 Pontefract Road
 Leeds
 LS10 1SW
 Email: admin@metconsultancygroup.com
 Phone: 0113 200 8900

Trial Pit Log

Trial Pit No
 TP10
 Sheet 1 of 1


Project Name: Manor Farm, Carburton

Project No.
 P21-00134

Co-ords: 461129.00 - 373359.00
 Level: 41.86

Date
 21/10/2021

Location: Manor Farm, Piper Lane, Carburton, S80 3BT



Scale
 1:25

Logged
 YK

Client: Wellbeck Estates Company Ltd

Water Strike	Samples & In Situ Testing			Depth (m)	Level (m)	Legend	Stratum Description
	Depth	Type	Results				
				0.20	41.66		Grass overlying medium brown silty gravelly SAND (TOPSOIL) with frequent rootlets. Sand is fine. Gravel is subangular to rounded fine to coarse of mixed lithologies.
				0.50	41.36		Light brown gravelly SAND (SUBSOIL) with moderate cobble content. Sand is fine. Gravel is subangular to rounded fine to coarse of mixed lithologies including brick. Cobbles are subrounded to rounded of mixed lithologies up to 120mm across. Whole bricks noted in the east of the trial pit at 0.5mbgl.
				1.40	40.46		Orangish light brown gravelly SAND with moderate cobble content. Sand is fine. Gravel is subrounded to rounded of mixed lithologies. Cobbles are subrounded to rounded fine to coarse of mixed lithologies up to 140mm across.
				1.40	40.46		Reddish orange slightly gravelly SAND with low cobble content. Sand is fine to medium. Gravel is subrounded to rounded fine to coarse of mixed lithologies. Cobbles are subrounded to rounded of mixed lithologies up to 90mm across. Layer of cobbles noted at 1.6mbgl.
				3.10	38.76		End of Pit at 3.10m

Remarks: Ground observed to be generally loose during excavation by JCB, potentially denser from 2.8mbgl. Terminated due to reach of JCB.

Stability: Unstable Weather: Clear

Trial Pit Photos

TP10

Manor Farm, Carburton

P21-00134



Photograph 29: TP10. Trial Pit.



Photograph 30: TP10. Topsoil Arisings.