



natural slates at 42° pitch

roof space

Horizontal Trespa Pura NFC boards

bedroom

bathroom

2150

SECTION THROUGH BEDROOM 1

high performance roof windows with solar control blinds

high performance roof windows with solar control blinds

roof integrated solar panels

natural slates at 42° pitch

2000 headroom to stairs

2000

1500

zinc alloy or coated steel rainwater goods

exhaust to mvhr

1135

sitting / dining / kitchen

service runs

254

"Lux Chalk" render

2000

utility / pantry

intake to mvhr

2400

tiled floor finish on power-floated 150 reinforced concrete slab on dpm on 200 Celotex insulation on dpm on sand blinded minimum 100 hardcore to fill - tbc

1000 access

Horizontal Trespa Pura NFC boards

slab supported on 450 piers of 2 no. 100 x 100 Foamglas Perinsul insulation at 1350 centres with Celotex Insulation between, insulating blockwork below down to foundation

1000 tbc

SECTION at STAIRS

24.01.2023 A. Finishes adjusted

Drawing:	Notional Sections	Scale:	1:50
Project:	Land adj. Faraway, 12 West Road, Dibden Purlieu Proposed New House A3 Drawing		

Haydn Bennett
Chartered Architect
24 Bedwin Street,
Salisbury, Wiltshire,
SP1 3UT
Tel: 01722 323925

Date:	06.2021
Drwg No.	205 - P07A

do not scale for construction - check all dimensions on site before construction