

Item: 11

CONVENTIONAL COTTAGE CASEMENT IN EUROPEAN REDWOOD

Quantity: 1

Style: DL101

Item Reference: Lounge (Front Left) SINGLE

Order Ref: 619TIM-8522-5-Brooks_-V6-E

Key Features:

See Drawing

Detailed Specification:

Width (mm)	895	Head Drip	20mm (included in overall ht)	Glass Pattern	Clear
Height (mm)	875	Head Drip Horns	5mm Left / 5mm Right	Glass Type	4mm Annealed (Single Putty)
Frame Head Size	60mm	Factory Fit Head Drip	Yes	Glazing Features	Astragal Squares
Feature Mould	Ovolo	Add Ons Required	No	Size of Bar	22mm (True Bar)
Colour	White (RAL 9003)	Trickle Vents Required	No	Handle	None
Cill	145mm x 68mm (Ext 55mm x 38mm)	Window Board Required	Yes	Hinge System	N/A
Cill Species	Engineered European Redwood	Window Board Species	Engineered European Redwood	FSC Certified	Yes
Cill Horns	45mm Left / 45mm Right	Window Board Colour	White (RAL 9003)		
Factory Fit Cill	Yes	Window Board Length (mm)	990		
		Window Board Width (mm)	85		

VIEWED FROM OUTSIDE. POINT OF ARROW DENOTES HINGE POSITION.

PLEASE CHECK THAT WE HAVE INTERPRETED YOUR REQUIREMENTS CORRECTLY. NO LIABILITY WILL BE ACCEPTED FOR ANY ERRORS THAT MAY OCCUR.