

Under Storey Woodland Seed Mix (EW1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Alliaria petiolata</i>	Garlic Mustard	1
<i>Anthriscus sylvestris</i>	Cow Parsley	0.5
<i>Carex divulsa ssp divulsa</i>	Grey Sedge	2
<i>Carex pendula</i>	Pendulous Sedge	0.1
<i>Chaerophyllum temulum</i>	Rough Chervil	4
<i>Digitalis purpurea</i>	Foxglove	1
<i>Filipendula ulmaria</i>	Meadowsweet	1.1
<i>Galium album</i>	Hedge Bedstraw	0.5
<i>Geranium pyreniacum</i>	Hedge Crane's-bill	2
<i>Geum urbanum</i>	Wood Avens	0.8
<i>Hyacinthoides non-scripta</i>	Bluebell	1
<i>Silene dioica</i>	Red Campion	5
<i>Silene flos-cuculi</i>	Ragged Robin	1
Grasses		
<i>Agrostis capillaris</i>	Common Bent	1
<i>Anthoxanthum odoratum</i>	Sweet Vernal-grass	2
<i>Brachypodium sylvaticum</i>	False Brome	1
<i>Cynosurus cristatus</i>	Crested Dogstail	50
<i>Deschampsia cespitosa</i>	Tufted Hair-grass	2
<i>Festuca rubra</i>	Red fescue	20
<i>Poa nemoralis</i>	Wood Meadow-grass	4

General Purpose Meadow Seed Mix (EM1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Achillea millefolium</i>	Yarrow	0.3
<i>Centaurea nigra</i>	Common Knapweed	1.5
<i>Leucanthemum vulgare</i>	Oxeye Daisy	1.5
<i>Malva moschata</i>	Musk Mallow	1.5
<i>Plantago lanceolata</i>	Ribwort Plantain	3
<i>Poterium sanguisorba (Sanguisorba minor)</i>	Salad Burnet	1
<i>Ranunculus acris</i>	Meadow Buttercup	0.2
<i>Rhinanthus minor</i>	Yellow Rattle	1
Grasses		
<i>Agrostis capillaris</i>	Common Bent	9
<i>Cynosurus cristatus</i>	Crested Dogstail	31.5
<i>Festuca rubra</i>	Red Fescue	27
<i>Phleum bertolonii</i>	Smaller Cat's-tail	4.5
<i>Poa pratensis</i>	Smooth-stalked Meadow-grass	18

Pond Edge Mix (EP1) 4gms/m		
Species	Common Name	% of the Mix
Wildflowers		
<i>Carex divulsa ssp divulsa</i>	Grey Sedge	2
<i>Carex pendula</i>	Pendulous Sedge	0.4
<i>Centaurea nigra</i>	Common Knapweed	2
<i>Cruciata laevipes</i>	Crosswort	2
<i>Dipsacus fullonum</i>	Wild teasel	0.4
<i>Filipendula ulmaria</i>	Meadowsweet	2
<i>Galium album</i>	Hedge Bedstraw	0.5
<i>Geranium pyreniacum</i>	Hedge Crane's-bill	1
<i>Geum rivale</i>	Water Avens	0.3
<i>Iris pseudacorus</i>	Yellow Iris	2.6
<i>Lycopus europaeus</i>	Gypsywort	0.4
<i>Oenanthe pimpinelloides</i>	Corky-fruited Water-dropwort	0.2
<i>Prunella vulgaris</i>	Selfheal	0.1
<i>Rhinanthus minor</i>	Yellow Rattle	0.5
<i>Silene dioica</i>	Red Campion	2.6
<i>Silene flos-cuculi</i>	Ragged Robin	3
Grasses		
<i>Agrostis capillaris</i>	Common Bent	2
<i>Anthoxanthum odoratum</i>	Sweet Vernal-grass	2
<i>Briza media</i>	Quaking Grass	4
<i>Cynosurus cristatus</i>	Crested Dogtail	48
<i>Deschampsia cespitosa</i>	Tufted Hair-grass	2
<i>Festuca rubra</i>	Red Fescue	22

Standard Trees - as shown on plans						
Species	Common Name	Type/Form	Girth	Height	Clear Stem	No.
<i>Acer campestre (Ac)</i>	Field Maple	RB/Std.	08 to 10	250-300	100-150	31
<i>Quercus robur (Qr)</i>	Pedunculate Oak	RB/Std.	08 to 10	250-300	100-150	30
<i>Quercus patraea (Qp)</i>	Sessile Oak	RB/Std.	08 to 10	250-300	100-150	33
<i>Sorbus aucuparia (Sa)</i>	Rowan	RB/Std.	08 to 10	250-300	100-150	28
TOTAL						122

Feathered Trees - as shown on plans						
Species	Common Name	Type/Form	Girth	Height	Clear Stem	No.
<i>Betula pendula (Bp)</i>	Silver Birch	BR/Feathered	< 6	200-250	N/a	122
<i>Prunus Avium (Pa)</i>	Wild Cherry	BR/Feathered	< 6	200-250	N/a	32
TOTAL						154

Native Woodland Mix - NW @ 1.5m centres (0.44 Plants per m ²)				NW1	NW2	NW3
			Area m ²	230	4380	1306
Species	Common Name	Type/Size	%	No.	No.	No.
<i>Acer campestre</i>	Field Maple	BR 1+1 /60-80	10	10	193	57
<i>Alnus glutinosa</i>	Alder	BR 1+1 /60-80	10	10	193	57
<i>Betula pendula</i>	Silver Birch	BR 1+1 /60-80	10	10	193	57
<i>Corylus avellana</i>	Hazel	BR 1+1 /60-80	10	10	193	57
<i>Crataegus monogyna</i>	Hawthorn	BR 1+1 /60-80	15	15	289	86
<i>Ilex aquifolium</i>	Holly	Container/2 ltr	10	10	193	57
<i>Prunus avium</i>	Wild Cherry	BR 1+1 /60-80	10	10	193	57
<i>Quercus robur</i>	Oak	BR 1+1 /60-80	15	15	289	86
<i>Sorbus aucuparia</i>	Rowan	BR 1+1 /60-80	5	5	96	29
<i>Tillia cordata</i>	Small-leaved lime	BR 1+1 /60-80	5	5	96	29
TOTAL			100	101	1927	575

Native Species-rich Hedgerow Mix - NH @7 plants/m (25cm centres, double staggered row)				NH1	NH2	NH3	NH4	NH5
			Length/m	136	72	93	55	200
Species	Common Name	Type/Size	%	No.	No.	No.	No.	No.
<i>Cornus sanguinea</i>	Common Dogwood	BR 1+1 /60-80	5	48	25	33	19	70
<i>Corylus avellana</i>	Hazel	BR 1+1 /60-80	10	95	50	65	39	140
<i>Crataegus monogyna</i>	Hawthorn	BR 1+1 /60-80	50	476	252	326	193	700
<i>Ilex aquifolium</i>	Holly	Container/2 ltr	10	95	50	65	39	140
<i>Prunus spinosa</i>	Blackthorn	BR 1+1 /60-80	20	190	101	130	77	280
<i>Rosa canina</i>	Dog rose	BR 1+1 /60-80	5	48	25	33	19	70
TOTAL			100	952	504	651	385	1400

Client Conrad Energy Limited				
Project Synchronous Condensers, Yaxley Application DC/22/04021 - Condition 13				
Drawing Title Landscape Mitigation - Planting Schedules				
Created by CL	Reviewer NR	Sheet Size A3	Scale NTS	Date Created 28.04.23
Drawing Nr. 059-12-03				Revision B
DRaW (UK) Ltd Morwick Hall York Road Leeds LS15 4TA t: 0113 8232871 www.draw-ltd.com				