

**Hopton Primary School, IP22 2QY** 

Yellow Fence A	Supply and install 52m (estimate) of green V-mesh fencing flush to conifer hedge @ 1.5m
	high.

Red Fence B	Supply and install 27m (estimate) of green V-mesh fencing directly in front of the existing
	fence @ 1.8m high.

Green Fence C Supply and install 27m (estimate) of close board fencing @ 1.8m to include concrete posts and concrete gravel board.

Replace gate and fence at front of school with green V-mesh fencing  $7m \times 1.8m$  high