

Client **Joshua Exley**

Job

| | | |
|--|---|------------------------------------|
| | <p>Screen</p> <p>Supply and fit new redwood casement window Flush Casement Frame 95mm x 56mm Mortice in Rebates Timber Type: Redwood with Sapele cill</p> <p>Screen Casement</p> <p>Screen Casement 56mm thick, frame rebate 60 x 15 Mortice in rebate, glass rebate 41 x 15, opening componets reduced by frame gap 2mm Timber Type: Redwood 4/14/4 - LowE - Argon - Silver bar - Clear Glass Toughened - Duplex</p> | <p>W'1</p> <p>×1</p> |
| | <p>Screen</p> <p>Supply and fit new redwood casement window Flush Casement Frame 95mm x 56mm Mortice in Rebates Timber Type: Redwood with Sapele cill</p> <p>Screen Casement</p> <p>Screen Casement 56mm thick, frame rebate 60 x 15 Mortice in rebate, glass rebate 41 x 15, opening componets reduced by frame gap 2mm Timber Type: Redwood 4/14/4 - LowE - Argon - Silver bar - Clear Glass Toughened - Duplex</p> | <p>W'2</p> <p>×1</p> |