

MATERIALS

WALLS: CAVITY CONSTRUCTION OUTER SKIN 115MM HAND MADE MULTI FACING BRICKS, RAISED ON 8-COURSES OF 200MM PLINTH BICKS. LAID TO ENGLISH GARDEN BOND WITH SNAP HEADERS WITH LIME RICH MORTARS AND 15MM LIME PUTTY STRUCK POINTING. 4- COURSE CORNER BRICK QUOINS.

OPENINGS: ALL GROUND FLOOR WINDOW AND DOOR OPENINGS WITH RUBBED AND GAUGED FLAT 4-COURSE ARCHES

ROOFS: MAIN ROOF: 42.5 DEG PITCHED ROOF WITH 500X250 NATURAL SLATES, LEAD ROLL HIPS AND RIDGES, LEAD FLASHINGS TO ABUDMENTS. LOWER ROOFS SIMILAR BUT SET AT 32-DEGREE PITCH

JOINERY: WINDOWS: PURPOSE MADE PAINTED TIMBER SASH AND CASEMENTS ON CAST STONE CILLS. FRENCH DOORS: SIMILAR TO CASEMENTS. PATIO DOORS: FULL HEIGHT POWDER COATED ALUMINIUM SLIDING FOLDING FRAMES ALL TRIPLE GLAZED FOR FULL INSULATION, FRONT DOOR 6-PANEL SOLID OAK

FACIAS / RAINWATER GOODS: FACIAS AND SOFFITS PAINTED TIMBER, ALL RAINWATER GOODS POWDER COATED ALUMINIUM, OGEE GUTTERS

PORCH: PURPOSE MADE CAST STONE COLUMNS FACIAS AND MOULDINGS, LEAD ROOF TO ROLLS. CAST STONE STEP AND PAVING

EAST ELEVATION 1

	WHEM	WHEMPS	FIELDS TEAD ROAD WARE – SG12	0PG	ALP ARIKOGLU RIBA Chartered Architect		
	PROPOSED REPLACEMENT DWELLING WD's BUILDERS WORK SET EAST ELEVATION 1				Kimpton Mill Codicote Hertfordshire SG4 8ST		7973 221 618 arikoglu.co.uk
0	0.5	1.0	2.0	3.0	JOB: 2022102 SCALE	E: 1:50 @ A3	2.12