



SOUTH ELEVATION 1

**MATERIALS**

**WALLS:** CAVITY CONSTRUCTION OUTER SKIN 115MM HAND MADE MULTI FACING BRICKS, RAISED ON 8-COURSE HIGH CAST STONE PLINTH : IN FLEMISH BOND WITH SNAP HEADERS WITH LIME RICH MORTARS AND 12MM LIME PUTTY STRUCK POINTING. 4- COURSE CORNER BRICK QUOINS.

**OPENINGS:** ALL FLOOR WINDOW AND DOOR OPENINGS WITH RUBBED AND GAUGED 4-COURSE CENTRED ARCHES

**ROOFS:** MAIN ROOF: 42.5 DEG PITCHED ROOF WITH 500X250 NATURAL SLATES, LEAD ROLL HIPS AND RIDGES, LEAD FLASHINGS TO ABUDMENTS. LOWER ROOFS SIMILAR BUT SET AT 32-DEGREE PITCH

**BALCONIES:** BRICK WORK CORNER SUPPORTS LAMINATED GLASS BALUSTER OGEE MOULDED PAINTED TIMBER HANDRAIL

**JOINERY:** WINDOWS: PURPOSE MADE PAINTED ACCOYA TIMBER SASH AND CASEMENTS ON CAST STONE CILLS. FRENCH AND PATIO DOORS: SIMILAR TO CASEMENTS, ALL GLAZED WITH 4/4/4 SLIMLITE SEALED UNITS WITH XENON GAS, FRONT DOOR 6-PANEL SOLID OAK

**FACIAS / RAINWATER GOODS:** FACIAS AND SOFFITS PAINTED TIMBER, ALL RAINWATER GOODS POWDER COATED ALUMINIUM, OGEE GUTTERS

**PORCH:** PURPOSE MADE CAST STONE COLUMNS FACIAS AND MOULDINGS, LEAD ROOF TO ROLLS. CAST STONE STEP AND PAVING

<p>HIGHFIELDS WHEMPSTEAD ROAD WHEMPSTEAD – WARE – SG12 0PG</p>	<p><b>ALP ARIKOGLU RIBA</b> Chartered Architect</p>
<p>PROPOSED REPLACEMENT DWELLING WD's BUILDERS WORK SET DOOR DETAILS 2</p>	<p>Kimpton Mill Codicote Hertfordshire SG4 8ST</p> <p style="text-align: right;">Tel 07973 221 618 email alp@arikoglu.co.uk</p>
<p>0    0.5    1.0    2.0    3.0M</p>	<p>JOB: 2022102 SCALE: 1:50 @ A3    <b>2.08-A</b></p>