

All sizes shown below are in plan view (measured horizontally).
 #1 is the first tread at the bottom.
 Stair width is over strings NOT including newel posts.
 All sizes must be checked against physical dimensions on site.
 You must allow a fitting tolerance.

Ref: Stackyard Barn

143.11kg
 (2pt)

Construction Detail



Standard (blocks and wedges)

Notes

Extras

Landing Full Post: 1no. (Square, inc. flat cap)
 Landing Half Post: 1no. (Square, inc. flat cap)

Assembly and Packaging

This Staircase is: *Assembled (Straight runs)*

Technical Details

Total Rise: 2500mm
 Individual Rise: 12 @ 208.33mm
 Individual Going: 231mm
 Staircase Pitch: 42.05 degrees
 Width Over Strings: 830mm

Specification

Strings: 27mm White Primed
 Treads: 22mm MDF Treads, 9mm MDF Risers
 Newels: 90x90mm White Primed (Square)
 Spindles: 41x41mm White Primed (Square)
 Handrail: 58x56mm White Primed (Cheshire patt)
 Baserail: 63x32mm White Primed (Cheshire patt)
 F. Tread: 22mm MDF Tread, 9mm MDF Riser



Longest Component: 3022mm (approx)
 [SB-ANXKU5D] 20230426 1311 35.246.87.105

The 3D Drawing below are for representation purposes only, some aspects may not be true. If you have any questions please call us.