




- Key:**
- Site boundary
 - 1.8m Closeboard fence
 - 900mm post & rail fence
 - Root protection area
 - Tree Protection Fencing
 - Grass
 - Paving slabs
 - Self Binding Gravel
 - Red Brindle Block Paving
 - Bark chippings



Proposed Planting Schedule

- Acer Campestre, 60-80cm, (10%)
 - Corylus Avellana, 60-80cm, (10%)
 - Crataegus monogyna, 60-80cm, (30%)
 - Ilex aquatulum, 60-80cm, (20%)
 - Prunus spinosa, 60-80cm, (30%)
- Whips to be planted at 5 per linear metre in double staggered rows 500mm apart.



GENERAL NOTES:

1.0 SOILS: Subsoil to be scarified to 300mm depth prior to spreading topsoil to alleviate compaction. Imported topsoil to be in accordance with BS3882 'Premium Grade' or as approved. As saved topsoil (and imported if requested) to be laboratory tested to BS3882 and ameliorated as required to meet the required specification. Screened or manufactured topsoil is not acceptable. Grass areas to be a minimum depth of 150mm, shrub beds 450mm depth and forestry/transplants 300mm depth. Incorporate proprietary non peat compost to BSI PAS 100 to 50mm depth evenly worked into soil.

2.0 EXISTING TREES: Where trees are to be retained they should be subject to a full arboricultural inspection to assess condition and safety. Retained trees shall be protected from damage by erection of 2.3m weldmesh fencing on a scaffold framework in accordance with BS 5837:2005 Fig 2. These barriers shall be maintained in position and in good condition until works are complete. Fencing to be located in accordance with Table 2 at a radius of 12 times the stem diameter (single stem trees) or 10 times the basal diameter (trees with more than one stem below 1.5m from ground) refer to Clause 5.2.2 Further precautions are to be taken as detailed within BS5837:2005 9.4

3.0 TREE SURGERY / REMOVAL: Tree surgery and tree removal to be carried out by a registered tree surgeon in accordance with BS 3998:1989.

4.0 TREE PLANTING: All trees to be in accordance with BS 3936 / 5236. Trees to be planted in accordance with BS4428 and securely staked using 2no tree stakes and tied using 2no straps per tree (No stake and crossbar type planting method should be used). Trees to be planted in pits 1000x1000x750mm backfilled with topsoil mixed with tree planting compost, ensuring tree pits are a minimum of 75mm deeper and 150mm wider than the tree roots. Base of pits to be broken up to a depth of 150mm. All trees to be container grown. The base of trees to be planted in grass areas are to be covered with 75mm depth bark mulch to 1.0m diameter and kept weed free.

5.0 SHRUB PLANTING: Plants are to be in accordance with BS3936 and handled in accordance with CPSE guidelines and planted in accordance with BS 4428. All plants to have a minimum of three breaks, except Hedera with a minimum of two. Well water plants immediately after planting and prior spreading of mulch. Shrub areas to be covered with 75mm bark mulch and kept weed free.

7.0 HEDGE PLANTING: Plants to be in accordance with BS3936 and handled in accordance with CPSE guidelines and planted in accordance with BS 4428. Hedge plants to be planted in double staggered rows 300mm apart at 450mm centres. Well water plants immediately after planting and prior spreading of mulch. Shrub areas to be covered with 75mm bark mulch and kept weed free.

8.0 TURFING: Grass turf areas to be Tillers 'Arena' or similar approved cultivated Topsoil to be cultivated and levelled as required and any debris or stones greater than 50mm diameter removed. Pre-turfing fertiliser to be applied in accordance with manufacturers instructions. Turf to be laid from planks with broken joint well butted up. Well water after laying to avoid shrinkage.

9.0 MAINTENANCE: To be carried out at approximately monthly intervals to include the following:

- Eradicate weeds by hand or chemical means
- Cut out dead or damaged stock or branches, prune as required
- Ensure all shrubs and trees are firmed in, securely staked and tied
- Collect litter, sweep and tidy site
- Apply suitable pesticides, fungicides and fertilisers as required
- Carry out grass mowing to turf when attained 100mm, cut to 35mm

| | | | |
|------|--------------|-----------|-------|
| X | FIRST ISSUE. | 15.05.23 | MB |
| Rev: | Details: | By / Chk: | Date: |

Copyright of this drawing is vested in J Mason Associates and it must not be copied or reproduced without formal consent. Do not scale off this drawing for construction purposes. All contractors and sub-contractors are responsible for taking and checking all dimensions relative to their work.

Notify J Mason Associates immediately of any variation between drawings and site conditions.

DO NOT SCALE OFF THIS DRAWING FOR CONSTRUCTION PURPOSES - IF IN DOUBT ASK.

Where drawings are based on survey information received, surveys are available on request.

All drawings to be read in conjunction with all relevant Structural and M&E Engineers drawings and specifications.

H&S HAZARDS:

Significant hazards relative to the architectural design shown on this drawing have been assessed and highlighted with reasonable skill and care using a warning triangle system.

This drawing is to be read in conjunction with all other hazards/risks which have been identified and recorded within the construction phase H&S plan.

It is assumed that all works on this drawing will be carried out by a competent contractor working, where appropriate, to an approved method statement.

Significant hazards are defined as:-

- Those not likely to be obvious to a competent contractor or other designers.
- Those of an unusual nature.
- Those likely to be difficult to manage effectively.

J Mason Associates

www.jmasonassociates.com
Tel: 01543 487798
J Mason Associates
St. Thomas House, Wolverhampton Road,
Cannock,
WS11 1AR

J Mason Associates
Registered in England & Wales
5053992

Client:
Ms Annie Marshall

Project:
Hay Lane Farm

Drawing Title:
Proposed Site Plan

| | | |
|----------------------------|----------------------------|---------------------------|
| Stage: RIBA 3 | Status: Planning | Sheet Size: A1 |
| Job Number: 2502 | Date: 15.05.2023 | Scale: As Noted |

Revision:
2502-03 -

