

From: Gary hammers66

garymarcks24@gmail.com

Subject: Lime Rendering Bildeston

Date: 13 May 2023 at 13:45:57

To: Adam Salisbury adam@fidgetsbarn.co.uk

Afternoon Adam

I hope all is well with you.

Please find below an estimated quote for the house and side of the public house.

House Road side (front):

Remove the render from the front of the property.

Remove the nails/screws.

Fix new sawn oak laths with lath nails.

Apply 20 mm backing lime render Therma lime.

Apply 10 mm top lime render Fine lime.

Labour cost £4,800

Materials cost £2,360 including delivery.

Total cost ££7,160

Side of public house:

Remove the render from the side of the building.

Remove the nails/screws.

Fix new oak sawn laths with lath nails.

Apply 20 mm backing lime render Therma lime.

Apply 10 mm top lime render Fine lime.

Labour cost £3,200

Materials cost £1,200 inc delivery.

Total cost £4,400

i hope this all makes sense to you.

I have tried calling the listing officer but no answer as yet.

It may be best to put in the application to gain their attention.

if i can help in any way please let me know.

Regards Gary

G.M.Plastering & Lime Rendering