

CHARLES NASH DESIGN AND MANAGEMENT SERVICES
35 BOWER HALL DRIVE STEEPLE BUMPSTEAD HAVERHILL SUFFOLK CB9 7ED

Application Ref: 3/22/0024/HH

Removal of section of boundary wall, brick piers and gate. Replace with a new wall using matching red bricks, matching red brick copings and matching Flemish bond, new black metal gate with brick piers either side.

Piggotts Farm Albury End Albury Ware Hertfordshire SG11 2HS

3. Prior to any building works being commenced samples of the external materials of construction for the development hereby permitted shall be submitted to and approved in writing by the Local Planning Authority and the development shall thereafter be implemented in accordance with the approved materials.

Proposal

Hand made bricks and copings by Bulmer Brick and Tile Company see attached photographs.

1. Lime putty based mortar ie
Site mixed mortar
NHL 3.5 > 1 : 2.5 (binder/sand ratio)

Clean, well graded sands (0-3mm)

2. Joint to be brushed flush ie to be finished to match existing.



EXISTING WALL

3. Joint width approx 10mm to match existing

4. Flemish bond to match existing.



SAMPLE BRICK TO MATCH EXISTING

5. A very similar condition to this one in respect of 3/22/0025/LBC has been discharged under X/22/0509/CND dated 8th February 2023.



SAMPLE BRICK TO MATCH