



**NOTE:**  
 PDL to provide a condition survey of all windows  
 Historic windows to be retained where possible  
 refer to Heritage report.  
 If new windows are required to be manufactured  
 then site sizes must be taken prior to manufacture

**Notes**

Do not scale from this drawing.

All dimensions are to be checked prior to construction and any discrepancies are to be identified to the Architect.

Copyright reserved.

**Window and External door Schedule**

- External Door and Screen 1  
Carriageway Entrance - new crital screen and doors refer to drawing 31001
- Window 2  
Room PDR - G.02 - retain existing sash and case window
- Window 3  
Room PDR - G.02 - retain existing sash and case window
- Window 4  
Room PDR - G.02 - retain existing sash and case window
- Window 5  
Room PDR - G.02 new crital door refer to drawing 31001
- Window 6  
Room RECEPTION - G.01 - to be retained
- External Door 7  
Room RECEPTION - G.01 - to be retained
- Window 8  
Room RECEPTION - G.01 - to be retained
- External Door 9  
Room RECEPTION - G.01 - to be retained
- Window 10  
Suite Lounge - 1.01 - retain existing sash and case window
- Window 11  
Suite Lounge - 1.01 - retain existing sash and case window
- Window 12  
Suite Lounge - 1.03 - retain existing sash and case window
- Window 13  
Suite Lounge - 1.03 - retain existing sash and case window remove opaque film from glass
- Window 14  
Suite Bedroom - 1.04 - retain existing sash and case window remove opaque film from glass
- Window 15  
Suite Bedroom - 1.04 - retain existing sash and case window
- Window 16  
Bathroom - 2.05 -
- Window 17  
Dressing Room - 2.04 -
- Window 18  
Bedroom - 2.02 -
- Window 19  
Bedroom - 2.02 -
- Window 20  
Bedroom - 2.01 - retain existing sash and case window
- Window 21  
Bedroom - 2.01 - retain existing sash and case window
- Window 22  
Plant room - 3.01 - retain existing window
- External Door 23  
Corridor - G.05 - existing timber entrance door to be retained
- Corridor - G.05 - timber sash and case windows retained replace glass with new clear glass.
- Window 25  
Corridor - 1.29 -
- Windows 29 and 30  
Stair 1 - G.05 -
- External Door 31  
Bedroom - 2.06 -
- Roof Window 32  
Bathroom - 2.07 - existing roof window to be retained
- External Door 33  
Corridor - G.05 - new crital door refer to drawing 31001
- Window 34  
Corridor - G.10 - original timber sash window to be retained, refurbish where necessary.
- Window 35 and 36  
Accessible WC - G.08 - original timber windows to be retained.
- Window 37  
Kitchen - G.11 -
- Window 38  
Kitchen - G.11 - new timber window size to match opening
- External Door 39  
Kitchen - G.11 - new timber leaf and half door to kitchen
- Windows 40 and 41  
Corridor - 1.31 - existing timber fixed windows to be retained, casement to be reinstated.
- Window 42  
Stair 2 - G.09 - existing fixed panel with top hung opening to be retained
- Window 43  
Sushi Bar - G.17 - timber casement window to be retained, replace frosted glass.
- External Door 44  
Sushi Bar - G.17 - replace existing timber door with new crital style door.
- Window 45  
Sushi Bar - G.17 - timber casement window to be retained, replace all blanks with new glass.
- Entrance Door 46  
Carriageway - new crital screen and doors refer to drawing 31001
- Window 47  
Bedroom - G.33 -
- Window 48  
Bedroom - G.33 -
- Windows 49, 50 and 51  
Bedroom - 1.22 - existing sash and case timber windows to be retained
- Windows 52, 53 and 54  
Bedroom - 1.20 - existing sash and case timber windows to be retained
- Window 106  
Stair 3 - new roof window ADV to escape stair

Revisions

Status  
**CONSTRUCTION**

Client  
**Paton Developments**

Project  
**The Bull at Burford  
 High Street, Burford,  
 Oxfordshire, OX18 4RG**

Title  
**Proposed  
 Window schedule sheet 1 of 3**

Scale	Size	Date	Drawn	Checked
1:50	A1	22/03/22	AG	DP

