



Specification type	uPVC Door	Contract number	NWC1705-274
Project Manager	Chris Bowen	Originated By	Compliance
Contract	PVCu Doors	Customer	Sovereign

Does the product need to be PAS:24 2016 certified?	Yes	U Values		CDM 2015
Does the product need to be Doc Q [PAS:24 2012 letterplate] certified?		Energy Rating		

Component List	Preferred Specification	Variant 1	Comments
Cavity Closer Depth	None		
Colour	White	As Per Survey	Any Colour other than white is to be agreed with the client
Profile Type	Bevelled(Chamfered)		
Outerframe Size	75mm		
Cill	Yes	As Per Survey	
Cill Size	As Per Survey		
Reinforcement	Thermal Insert - uPVC	Steel to Sash	
Handle Type	Mila Pro secure	Lever/Lever	off-set Split Spindle
Handle Colour	White		
Hinges	SFS 2D		
Hinge Colour	White		
Lock	Avantis		
Cylinder	Yale Kitemarked		
Drainage	Base Drainage		
Trickle Vent Type			
Trickle Vent Position			
Bead Type	Ovolo		
Glass Type	6.8 LAM/18/4 Tough	Glass Clips	
Glass Pattern	Cotswold		
Glass Delivery Method	Loose		
Glass Additional Info	Free Type		
Panels	As Per Survey		
Couplers	As Per Survey		
Knock-Ons	As Per Survey		
Single/Double	Single and Double		
Threshold	Low Aluminium	As Per Survey	

Additional Items	<p>Specification is applicable to both Single and Double Doors PVCu doors are applicable for rear doors only. Although the use of composite doors in place of single rear PVC doors is currently being evaluate by the client Cat Flaps are permitted in rear doors only (client understands that this will remove PAS24 compliance) If profile is other than white gold handles to be used.</p>
------------------	---