

5 Sparrowhawk Close  
 Ewshot  
 Farnham  
 GU10 5TJ



**AFA Consulting Ltd**

105 Ambleside  
 Lightwater  
 Surrey  
 GU18 5UJ

Phone: 0800 772 0303  
 Mobile: 07515920686  
 info@afaconsultingltd.com

**General Tree Assessment (Summary)**

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Priority	Done	Inspected
T1	Oak	19.2	8	M	Fair	See Comment :: Unspecified	1 year	No	19-Jul-23
<p>Comment: A mature Oak tree situated at the rear of the property and immediately adjacent to the western boundary. Some canopy decline visible in upper northern canopy. Large dead limbs also visible throughout canopy which should be removed. The south and eastern radial spread is becoming overlong with canopy bias noted. This section of canopy should be reduced by a maximum of 2.5m to rebalance the canopy, reduce any likelihood of limb shedding and allow for natural light infiltration which will benefit shaded border beneath. There is some overlong radial spread noted in the western canopy which should also be reduced by a maximum of 2.5m. A maximum reduction of 1m is advised in the upper canopy. The current height and radial spread are 19 and 9.5 metres respectively. These will be no less than 18 and 7 metres respectively following remediation pruning. The low eastern canopy is shading the border beneath. This should be lifted to 4m.</p>									
T2	Oak	15	4	SM	Fair	Raise low canopy :: To 4.0m	1 year	No	19-Jul-23
<p>Comment: A semi mature Oak tree situated at the rear of the property and forming part of a group of trees. Satisfactory habit and vitality. Being suppressed by surrounding trees. Low eastern canopy is shading border beneath and should be lifted.</p>									
T3	Oak	15	4	SM	Poor	Fell :: Fell to ground level	1 year	No	19-Jul-23
<p>Comment: A semi mature Oak tree situated at the rear of the property and forming part of a group of trees. Some canopy decline visible in upper canopy with sparse growth. Very poor habit and vitality. Being suppressed by surrounding trees and has no long term retention value. Removal advised.</p>									
<p><b>Age Classification:</b> NP Newly planted EM Early Mature SM Semi-mature OM Over Mature          Y Young M Mature</p> <p><b>Condition:</b> Overall unless specified as - C Crown S Stem B Basal area</p>									

Tree Ref	Species	H (m)	Spr (m)	Maturity	Condition	Action Recommendations	Priority	Done	Inspected
T4	Oak	16	5	M	Poor	Fell :: Fell to ground level	1 year	No	19-Jul-23
<p>Comment: A mature Turkey Oak tree situated at the rear of the property and forming part of a group of trees. Very poor habit with pronounced lean to the east (towards the dwelling). Being suppressed by surrounding trees and has no long term retention value due to growth habit. This tree will soon outgrow its environment and is not a native species. Removal of this tree will reduce the shade being cast on the border beneath and will also benefit the Beech tree situated immediately west. Removal advised.</p>									
T5	Oak	16.5	5	M	Fair	Fell :: Fell to ground level	1 year	No	19-Jul-23
<p>Comment: A mature Turkey Oak tree situated at the rear of the property and forming part of a group of trees. Drawn up habit due to competition with adjacent Beech tree. Being suppressed by surrounding trees and has no long term retention value due to growth habit. This tree will soon outgrow its environment and is not a native species. Removal of this tree will benefit the Beech tree situated immediately south and as it will allow it to develop a full and balanced canopy. Removal advised.</p>									
T6	Beech	18	8	M	Fair	Raise low canopy :: To 4.0m Reduce lateral limbs :: By 25% to shape	1 year 1 year	No No	19-Jul-23
<p>Comment: A mature Beech tree situated at the rear of the property and forming part of a group of trees. Low eastern canopy is shading border beneath and should be lifted. Reduce overlong primary limb in northeast canopy by 2.5m.</p>									
T7	Holly	15	2	M	Poor	Fell :: Fell to ground level	1 year	No	19-Jul-23
<p>Comment: A declining Holly tree situated at the rear of the property and forming part of a group of several Holly trees. Declining tree unlikely to survive. Removal advised.</p>									
<p><b>Age Classification:</b> NP Newly planted EM Early Mature      <b>Condition:</b> Overall unless specified as - C Crown  Y Young M Mature      S Stem  SM Semi-mature OM Over Mature      B Basal area</p>									