

Wall ties at 225c/s positioned as shown.

selected flint facings

cavity tray

2 course Brick header, True Arch.

Brick to bed joint reinforcement

Mastic sealant

Arch to be supported on temporary 3/w camber (shown dotted) during construction, spiked to permanent camber screwed into window head. Camber to be treated with 3 coats wood preservative prior to building in & decoration.

90mm (min)

50mm cavity insulation

use standard catmic Lintel CN55 over opening. check on working drawing for type & size.

insulate void to Lintel.

plaster finish

Mastic sealant

parment cill to have a min slant of 10° & a min overhang of 40mm.

40mm

DPM shown dotted

Insulation

SCALE = 1 : 5

Robert Lord Associates

4 The Boulevard, Sheringham, Norfolk, NR26 8LH

Tel: (0263) 822276/823365

Sill & HEAD DETAIL FOR FLINT, BRICK & BLOCK CAVITY WALL.

(Using standard Lintel CN55).

drawn JTC	job no. 50	dtg. no.
-----------	------------	----------