

Rural Multi

Classic Brick Code: BRKRM(MET or IMP)

Production Type: Through Coloured Red & Orange Handmade Clay

Blend Ratio: 50% Orange / 25% Red / 25% Dark Multi

Specification: BS EN 771-1

Size: 215 x 102.5 x 65mm
230 x 110 x 68mm*



Dimensional Tolerance: T1

Durability: F2

Range: R1

Reaction to Fire: Class A1

Compressive Strength:
46N/mm2 Mean

Bulk Density: 1530Kg/m

Water Absorption: Mean 13%

Pack Size: 450No
360No*

Soluble Salts: S2

Pack Weight: 1049kg
995kg*

Good practice from relevant British Standard relating to design & workmanship must be observed. Liability cannot be accepted for the performance of our product if the above is not adhered to.