

## WILLIAMS & HENRY PROPERTY maintenance todd

Litton house saville road peterborough

ESTIMATE

EST0928

Mar 8, 2022

## Jo

21 Main Street, Woodnewton PE8 5EB

07816230733

jo.pannett21@gmail.com

DESCRIPTION	RATE	QTY	AMOUNT
Scaffolding erected to the full back roofline.			
All existing felt and boards removed from all flat roofs and side cheeks of all four dormers on the back rooff.	F		
Roof tiimbers checked on all dormers Any damage timbers replaced where needed.			
New kingspan insulation fitted to all Flat Roofs and Dormer cheeks.			
New 18mm @SB sterling boards fitted to all Dormers.			
New Code 5 Lead fitted to all Flat Roofs and cheeks on Dormers.			
Remedial works to collyWeston slates around all dormers. Price includes all labour plus materials plus scaffolding and disposal of al waste.	II		

All work guaranteed for eight years.