



TALLOW BOUND LIMEWASH (CONCENTRATED LIMEWASH PLEASE READ FULL APPLICATION GUIDELINES)

TECHNICAL DATA SHEET

DESCRIPTION	A limewash made from mature pure filtered slaked lime, modified with tallow to the Suffolk Preservation Society recipe.
PERFORMANCE & USE	Exterior application to lime render, wattle and daub, clay lump surfaces also on to give a breathable decorative finish with good water shedding properties.
COLOUR RANGE	Colour cards & colour matching.
FINISH	Matt.
SPECIFIC GRAVITY	1.2.
STORAGE	Between 5 & 25°C. Indefinite shelf life in unopened containers.
DRYING TIME	4 hours @ 20° depending on airflow and humidity.
OVERCOATING TIME	24 hours.
THEORETICAL SPREAD RATE	9m ² per litre per coat.. (based on dilution rates and application guidelines)
COATS	Recommended 3 coat system. (Please read application guidelines)
PACK SIZE	120ml (tester pot), 2.5, 5 & 10 litres
THINNER/CLEANER	Water
APPLICATION METHOD	Brush (2 knot brush or good masonry brush)

Information given is based upon formulations in use at time of printing. We reserve the right to modify any product without notice although in the case of any major modification a new data sheet will be issued.