



**Notes**

**Floodlighting Equipment**  
 6 x 15m Masts (M1-M6)  
 Each carrying the following Floodlights :-  
 M1,M3,M4 & M6.....  
 1 x Siteco FL11 Pro 3 Brick  
 1 x Siteco FL11 Pro 2 Brick  
 M2 & M5.....  
 2 x Siteco FL11 Pro 3 Brick

**Illuminance Levels**  
**Initial** -  
 (100hrs) E.i.ave = 227Lux  
**Maintained** -  
 (4000hrs) E.i.ave = 204Lux

**Uniformity**  
 Emin/Eave = 0.60

Grid values in Lux(initial).  
 Grid interval = 5m.  
 Contour values in Lux (initial).  
 Contours: 5, 15, 25, 50 Lux.

**Maintenance Factor = 0.90**

www.halliday-lighting.co.uk	
Project Bede Academy	
Drawing Title Proposed floodlighting	
Drawn By (print) JS	Date 05/07/23
Project No 6408	Scale 1:750 @ A3
Drawing No HLS6408	Status Proposal

www.halliday-lighting.co.uk	
Project Bede Academy	
Drawing Title Proposed floodlighting	
Drawn By (print) JS	Date 05/07/23
Project No 6408	Scale 1:750 @ A3
Drawing No HLS6408	Status Proposal

Notes:  
 Line marks  
 NR-11V  
 NR-99B  
 NR-7V  
 NR-5  
 NR-80  
 NR-5  
 NR-80