

# PERIOD RESTORATION

*Specialists in the traditional restoration of historic buildings*

## Method Statement

Folly Cottage, Andover, SP11 0RQ

Project: Stripe old existing paint from property elevations.

### **Scope:**

- a. To use supplied platforms, Hop-ups, Towers to access building elevations.
- b. At all times use correct PPE equipment, Overalls, Gloves, Safety Specs etc.
- c. Create Test Panel 1m<sup>2</sup>
- d. Assessment of substrate condition after test panel.
- e. If Substrate is ok, Brush off masonry walls.
- f. Application of product to follows per manufactures recommendation.
- g. Scrape off with hand tools.

### **Delivery, Storage, Handling:**

- a. Local pick up from manufacturer.
- b. Manufacture COSH statement.
- c. COSH docs attached

### **Surface Preparation:**

- a. After removal using clean water to remove all residue from striper.
- b. Apply limewash.
- c. Colour to be off white.
- d. Apply lime wash with Brush
- e. no: 3 coats of limewash

### **Product:**

- a. **Peel Away 7 Paint Remover** product data attached.
- b. [Peelaway 7 \(Architecturally Specified\) | Peel Away](#)

### **Repair Work:**

- a. Repair work if required will be done in-accordance with traditional methods repaired as per existing construction make up. Like for like!
- b. To contact Conservation.

### **Environmental Considerations:**

- a. COSH docs attached
- b. Waste material to be bagged and skipped away on site, which will be removed by registered waste carrier.

