



C= External cement render to be removed in strips by hand. Monitor stability of cob. Replace with a lime putty render with hair backed coats and a float coat of unhaird lime. Paint with compatible, breathable paint system. Render by specialist conservation builder. Refer to method statement.

D= cement plaster to be removed from annex and north walls of house and conservatory area, replace with new lime putty render and breathable paint system. Render by specialist builder. Refer to method statement.

No existing skirting to annex. Render to continue to floor level, and no new skirtings to be installed.

Read in conjunction with the asbestos report, schedule of work + structural engener's drawings.

AMM ANNIE MARTIN ARCHITECT

VENBRIDGE HOUSE, CHERITON BISHOP

Proposed ground floor Annex plan

201 1:50 @ A3 APRIL 2023

ANNIE MARTIN ARCHITECT
CHERITON BISHOP, EXETER EX6 6HN
01647 272839