



Product Information

| | |
|------------------------|------------------------------------|
| Ibstock Code: | A2602A |
| Type: | Machine Moulded Waterstruck |
| Facing Description: | Distressed |
| Dry Brick Weight (kg): | 2.7kg |
| Pack Quantity: | 392 |
| Packaging (standard): | Banded (Plastic) and Shrinkwrapped |
| Factory: | Birtley |

Technical Specification (to BS EN 771-1)

| | |
|---|------------|
| Brick Dimensions (L x W x H mm): | 215x102x65 |
| Size Tolerances Mean & Range: | Tm Rm |
| Configuration: | Solid |
| Voids (%): | 0 |
| Compressive Strength (N/mm ²): | 20 |
| Active Soluble Salts: | S2 |
| Water Absorption (% weight): | 12 |
| Durability: | F2 |
| Gross Dry Density (Sound Insulation) (Kg/m ³): | 1740 |
| Equivalent Thermal Conductivity "K" value 5% Exposed: | 0.86 |
| Initial Rate of Absorption (Suction Rate) (Kg/m ² /min): | 0.6 |
| EAN: | 5.04E+12 |