

# Fire Strategy Document

## 37 Hichisson Road, London SE15 3AN

Prepared by. Mr M McHugh MCIOB MCABE who has worked in Building Control for over 25 years at Tower Hamlets Building Control, Carillion, HCD Building Control and was also Director and shareholder at a Corporate Approved Inspector - LB Building Control.

He provides Building Regulations and Fire Safety advice for clients such as The Cabinet Office, Pizza Express and City Lit.

He has successfully completed similar Planning Fire Strategy Documents in Greater London

### 1. General comments.

37 Hichisson Road, London SE15 3AN is a 3 storey detached property with existing solid brick construction, timber structural floors, plastered walls and a tiled roof.

The proposal is to replace the existing back addition with a new extension using traditional materials such as cavity masonry. The roof will be pitched and contain 3no. Velux windows.

The extension will reuse the existing as only boundary wall.

The building is currently and will remain a single family dwelling.

### 2. Information on space provisions for fire appliances and assembly points (criteria 1).

Fire Brigade Access is via the front entrance on 37 Hichisson Road, London SE15 3AN. The width of the road is greater than 3.7m and therefore complies with Approved Document B1 Table 13.1.

Although the extension increases the distance for the Fire Brigade hose it is well within the 45m requirement contained in Approved Document B1 clause 13.1. The extension replicates many similar developments in the area.

*13.1 For dwellinghouses, access for a pumping appliance should be provided to within 45m of all points inside the dwellinghouse*

### 3. Information on passive and active safety measures (criteria 2).

Heat and smoke detection will be provided in accordance with BS5839 Part 6 within the extension and entrance area and a heat detector provided in the kitchen.

An FD20 door will be provided to the kitchen and this will be independently certified (in accordance with BS476 Part 22). This will maintain the protected escape route.

**4. Information and data on construction products and materials (criteria 3).**

Walls to the side elevation of the extension will comprise a cavity masonry wall which provides 60 minutes fire protection. This is in accordance with Approved Document B1. Wall insulation will be mineral wool which is non combustible.

The pitched roof is glazed with 3no. velux windows with glass greater than 4mm so are graded as BROOF(t4) in accordance with table 12.1 of Approved document B1.

Ceiling linings will be plasterboard which typically achieves a class B – s3, d2 European classification or Class ) ( National Classification).

Structural steel work will be encased in fireline plasterboard to achieve 30 minutes fire protection in accordance with table B4 of Approved Document B1.

**5. Information on means of escape and evacuation strategy (criteria 4).**

Means of escape from the kitchen / dining area is via the entrance hall and the final exit / entrance door.

The above is fully compliant with Approved Document B1.

**6. Information on access and equipment for firefighting (criteria 6).**

Access to the property will be via the front door.

Due to the low height of the premise this is acceptable and there is no requirement to fit hydrants or provide firefighting equipment or shafts etc.

No alternative water supply is required and on street hydrants will be utilised.