

Specification of new front door – 86 High Street Tarvin

Replacement front door set – Cheshire Joinery Services Limited

Remove the existing door and frame. Manufacture and install a new door set in kiln dried Sapele hardwood on a like for like basis. The door is traditional mortise and tenon jointed 57mm thick section in-filled with double ex 1” T&G boarding with an insulated core. The door is pre-hung in the frame on a jig in our workshop and is fitted with hardware from our standard range including roller bearing hinges, a Yale latch lock with finger pull, a BS five-lever mortise dead lock with escutcheons, a ring door knocker and no letter plate and tidy. The frame opening is sealed with Aqua-seal weather excluder and a low-line threshold bar. The timber is supplied in spray applied primer undercoat with the option for two colour topcoat for the Sapele option – this will be coloured Vert de Terre (Farrow and Ball 2023). Any requirements for making good will use approved lime mortar in line with G2LB guidance.