








**KEY TO FENCE TREATMENTS**

- Existing fences and boundary treatments to be retained
- Timber post and 3 rail fencing 1100mm high in accordance with BS1722-Part 7. Timber to be rough sawn timber pressure impregnated to give a 25 year life - Natural colour. SEE DETAIL B/03
- On river bank fence is to have 100mm square mesh stapled to inside fence
- 2200mm high timber feature fence to provide screening between terraces to have horizontal boarding both sides generally as BS1722-Part 6. Timber to be planed all round and treated with Sodalife Extra Durable Clearcoat or similar approved in accordance with supplier's specification. Colour - Clear, satin finish. SEE DETAIL C/03
- 1200mm high timber palisade fence on concrete posts in accordance with BS1722-Part 6. Timber is to be rough sawn, pressure impregnated to give 25 year life. Natural colour. SEE DETAIL A/03
- Metal hoop top railing 1100mm high along top of retaining wall to river bank in accordance with BS1722-Part 9. Colour Black RAL 9005. SEE DETAIL D/03
- Where fence extends beyond retaining wall freestanding hoop top railing is to be 1200mm high. SEE DETAIL C/03
- 1100mm high mesh screen and quadrant (Colour black RAL 9005) around top of terrace wall to architect's details.
- 1800mm high Paladin, weldmesh security fencing to perimeter of enclosed terrace in accordance with BS1722-Part 14 and architect's details. Colour black -RAL 9005.
- 900mm high mild steel circular hollow section handrail to ramps. To be galvanised and polyester powder coated. Colour black -RAL 9005. SEE DETAIL F/03



V3 Revised detail to hoop top railing. Handrail added. Fence to top of river bank outside site boundary not shown. DR 29-0  
V2 Fence added to top of southern bank to river DR 08-0  
Rev. Description Auth. C  
Date: July 2022

Client: Mace  
Project: Abbey Fields Leisure Centre

Title: Proposed boundary treatments plan and details  
Map file reference DWG No  
211221 0882 LAND V3 L003

**WHARTON**  
Working in partnership with  
**mood** landscape  
THE COACH HOUSE | THE OLD VICARAGE | BIRMINGHAM ROAD  
COUGHTON | WARWICKSHIRE | B49 5HU  
E. info@mnic.co.uk  
T. +44 (0)1789 459468  
www.wnic.co.uk