

## 1279-902 - External Materials & Finishes Schedule

Issued: P3 - 29.09.2023 - Issued for Planning



SIMON MORRAY-JONES

### Keys:

	Room works to be done in next Phase of Works - Works not included in this application
	Room works done in previous Phase of Works - Works approved in previous applications
	Room not affected by proposed works

Item	Building Reference	Floor	Roof	Walls	Status
01	Main Cottage	<b>South Terrace:</b> 600mm width x Random lengths Reclaimed limestone flags with Irregular widths mortar joints <i>Finish: Tumbled</i>	N/A	N/A	Works approved in writing by LPA. Ref. 2022/2414/APP
02	East Wing	<b>South Terrace:</b> 600mm width x Random lengths Reclaimed limestone flags with Irregular widths mortar joints <i>Finish: Tumbled</i>	Reclaimed Roman clay tiles to match existing	Rubblestone stone walling: Stone & mortar specification to match existing. Refer to sample on site for approval	
03	West Wing	<b>South Terrace:</b> 600mm width x Random lengths Reclaimed limestone flags with Irregular widths mortar joints <i>Finish: Tumbled</i>	<b>Dormer roof:</b> Existing or Reclaimed Roman clay tiles to be used to match existing	<b>Dormer external walls:</b> 20mm Untreated Grade A Siberian larch feather edge boards <i>Finish: Fine-sawn</i>	Works approved in writing by LPA. Ref. 2022/2414/APP
04	Barn	N/A			
05	Glasshouse	N/A			
06	Courtyard	150mm width x Random lengths Blue lias cobblestone paving with Irregular widths mortar joints <i>Finish: Tumbled</i>	N/A	N/A	Works approved in writing by LPA. Ref. 2022/2414/APP
07	Barn Courtyard	N/A			