



Ext/int profile colour	Stock RAL7016M
Roof glazing	4mm Neutral Solar Self Clean -16mm(BWE) Gas- 4mm Low E (TBS)
Glass area	7.24m <sup>2</sup>
Top cap material	Aluminium
Top cap style	Flat
Rafter / hip type	4001A
Ridge type	4002A
Finial type	None
Cresting type	None
Roof vent type	Electric with rocker switch
Ring beam type	Slim
Sill type	None
Top of frame to U/S ridge	382mm
Top of frame to top of ridge	519mm (Excl Crest)
Roof slope	25.0°

1. All LANTERN dimensions are to EXTERNAL KERB unless otherwise stated.
2. All LEAN-TO, FLAT ROOF LEAN-TO, SKYROOM dimensions are to INTRNAL unless otherwise stated.
3. The support structure for this roof must provide the necessary lateral and axial stability in accordance with the relevant British Standard. Guidance if required should be sought from your frame supplier.
4. All roof vents are aluminium externally and PVC internally unless otherwise stated.

Please check the specification and dimensions shown herewith with care and confirm your acceptance by signing here

SIGNED :

DATED :

If you are unsure of any detail appearing herewith please query the Atlas roof department. Tel 02838 327741 Fax 02838 324358

**ATLAS**  
MORE SKY LESS ROOF™

Version 5.656

Atlas Glazed Roof Solutions,  
a division of Customade Ltd,  
Oldends Hall, Oldends Lane,  
Stonehouse  
028 38 327741  
028 38 324358  
Joanne.wilson@atlasroofsolutions.co.uk

Quote Number	040.121023.5
Order Number	
Customer Reference	39575
Draughts Person	Joanne Wilson
Process Date	12/10/2023
Site Post Code	
Customer Name	Roofglaze Rooflights