



POZILIME LIMEWASH (CONCENTRATED LIMEWASH PLEASE READ FULL APPLICATION GUIDELINES)

TECHNICAL DATA SHEET

DESCRIPTION	An external limewash made from pure filtered slaked lime with a pozzolanic additive modified with minimal linseed oil and synthetic polymer resin for increased adhesion and water shedding properties.
PERFORMANCE & USE	For application onto difficult surfaces, cement render, already painted surfaces etc as well as traditional lime render and wattle and daub. Gives traditional limewash finish across lime renders as well as difficult surfaces giving good breathability where needed as well as adhering to the modern surfaces and coatings. Pozilime has a slight textured finish due to the pozzolanic additive.
COLOUR RANGE	Colour cards & colour matching.
FINISH	Matt.
SPECIFIC GRAVITY	1.2.
STORAGE	Between 5 & 25°C. 6 month shelf life in unopened containers.
DRYING TIME	4 hours @ 20° depending on airflow and humidity.
OVERCOATING TIME	24 hours.
THEORETICAL SPREAD RATE	9m ² per litre per coat (based on dilution rates and application guidelines)
COATS	Recommended 3 coat system. (Please read application guidelines)
PACK SIZE	120ml (tester pot), 2.5, 5 & 10 litres
THINNER/CLEANER	Water
APPLICATION METHOD	Brush (2 knot brush or good masonry brush)

Information given is based upon formulations in use at time of printing. We reserve the right to modify any product without notice although in the case of any major modification a new data sheet will be issued.