

existing sash removed  
 & replaced with aluminum  
 double glazed unit

existing sash stopped off  
 & replaced with new sash



existing windows removed  
 & opening built up with  
 brickwork to match  
 existing

fan extract

boiler extract

existing sash adjusted.

Side Elevation

existing external door  
 removed & opening  
 adjusted with new  
 upvc double glazed  
 casement window  
 installed with double  
 glass.

new composite external  
 door in adjacent  
 opening

existing windows replaced  
 with new double glazed  
 casement windows with  
 double glass

revision	A	design solution changed from a self contained studio apartment to an extension of the existing apartment
----------	---	--

client	Mr & Weatheritt	scale	1:50 @ A3
address	9g Priors Terrace Tynemouth NE30 4BE	drawn by	iwg
plan	Proposed Side Elevation	date	Feb 2023
Do not scale off this drawing and read in conjunction with the associated Detail Specification		drawing no	9
		revision	A