



TECHNICAL SPECIFICATION - ECOLUX MINI

**LED STRIP**  
 Latest high lighting chip giving 1650 Lumens per metre LED output. Only 14.4 watts per metre power consumption 75% energy saving compared to Fluorescent.

24 volt input, less current less voltage drop. 6000k cool white or 3000k warm white 120 degree angle.

IP65 protected, 50,000 hours+ lamp life. 5 year Warranty.

Full CE certification and ROHS compliant.

**DRIVERS**  
 Epoxy encapsulated fully isolated case with IP67 protection. Constant voltage design. Short circuit, over current, over voltage protection. Fitted onto quick release slide in Gear Trays. Full CE certification and ROHS compliant.

**LIGHT FITTING**  
 Specially designed 45mm aluminium extrusion supplied up to 6000mm lengths which can be joined together using cast aluminium connectors.

Die cast aluminium end caps with rear cable entry standard 300mm multi brackets.

Snap-in polycarbonate 90 degree magnifying lens diffuser. Casing sealed and certificated to IP65.

Full CE certificate and 5 year parts warranty. Conforms to BS EN 60598-1:2015 and BS EN 60598-2-1:1989 'UK Deviations Only'.



15 Barnes Wallis Rd, Fareham  
 Hampshire PO15 5TT  
 Tel: 023 8023 2311  
 Web: www.innovatesigns.co.uk  
 Email: info@innovatesigns.co.uk

Client	One Stop Stores			Title	Proposal	Rev	Date	Description	Drw By
Site Name	Cheltenham, Benhall Avenue			Date	18/10/2023	B	09/10/23	Remove window vinyls [D]to[G] and reduce to HH window vinyls [B]&[C] and remove 'Eat Street'	IW
Job No.	22751	Epos Code	6697	Drawn	IW	C	12/10/23	Vinyl [C] swap to spaghetti & new vinyl [D]	IW
Proj Type	Franchise			Approved	18/10/23	RC	D	18/10/23	Removed perimeter 'brick' - graphic
PM	GP	Designer	RC	Drwg No.	E	E	18/10/23	Reinstate perimeter 'brick' - graphic	IW

**This drawing is for approval purposes.**  
 Please check all details noted on the drawing including spelling, and provide written confirmation of your approval to an **Innovate Signs Project Manager**. Once approved production will commence based on the approved drawing. Any changes made after production has begun will incur an additional cost.