



KEY:

- EXISTING SHRUBS**
- NEW NATIVE WOODLAND PLANTING TO SCHEDULE**
- WILDFLOWER PLANTING**
SCOTTISH LOWLAND MEADOW MIX BY SCOTIA SEEDS OR APPROVED EQUIVALENT @ 4g/m²
- POND PLANTING TO SCHEDULE**
- MIXED NATIVE HEDGE**

Management & Maintenance Schedules													
ESTABLISHMENT MAINTENANCE: First two years undertaken by selected contractor;													
Operations	Months											Operations per year	
	J	F	M	A	M	J	J	A	S	O	N		D
GENERAL REQUIREMENTS													
Leafing out inspection, plant material not leafed out shall be replaced by the contractor at his own cost during plant replacement operations							√						1
100% of plant material to be present at handover													8
90% vegetation free 1m circle centred on each plant to be maintained around planting including mulch cover during establishment period & for extent of contract duration			√	√	√	√	√	√	√	√			2
Hand weed inside shelters							√						2
Check stakes, ties and guards, adjust as required				√									As required
Water at frequency to ensure establishment and survival				√	√	√	√	√	√				2
Firm plants & keep vertical as required				√					√				As required
Clear plant stations and planting areas of litter				√	√	√	√	√	√	√			2 or as required
Check all plants for signs of pest, disease or nutrient deficiency & seek expert advice as required						√				√			1 or as required
Plant replacements: planting that has failed or is damaged by herbicide application should be replaced during the next growing season											√		TBC
Pruning: all planting material to be checked for damage to branches, shoots & bark. All dead, damaged branches/shoots or epicormic growth to be cleanly cut back to sound, undamaged wood. All tree works to be undertaken in accordance with BS 3998: 1989. Prunings & trimmings to be removed from site												√	1 or as required
Remove plant shelters, to be confirmed by Landscape Architect						√							1 or as required
INDIVIDUAL TREE PLANTING													
Check stakes & ties; replace loose, broken or decayed items to original specification. Adjust, refix or replace loose or defective ties, allowing for growth and to prevent chafing. - Where chafing has occurred, reposition, or replace ties to prevent further chafing											√		2
NATIVE MIXED HEDGING													
Trim to 60cm height after planting, maintain at 1.5m with slight batter to top, trim any rangy branches to 60cm width				√								√	10
WILDFLOWER/GRASSES SEEDING													
One cut in the first year, in late September, remove arisings off site											√		4
LITTER PICKING													
GENERAL MAINTENANCE: From years 2 to 10; After 10 years we suggest the maintenance regime is revised to ensure best practice and relevance to the stage of development of the landscape.													2
Operations	J	F	M	A	M	J	J	A	S	O	N	D	No of operations
90% vegetation free 1m circle centred on each plant to be maintained around planting including mulch cover.				√	√	√	√	√	√	√			2
Check stakes, ties and guards, adjust as required				√						√			2 or as required
Firm plants & keep vertical as required				√						√			1 or as required
Check all plants for signs of pest, disease or nutrient deficiency & seek expert advice as required						√				√			1 or as required
Plant replacements: planting that has failed or is damaged by herbicide application should be replaced during the next growing season											√		1 or as required
Pruning: all planting material to be checked for damage to branches, shoots & bark. All dead, damaged branches/shoots or epicormic growth to be cleanly cut back to sound, undamaged wood. All tree works to be undertaken in accordance with BS 3998: 1989. Prunings & trimmings to be removed from site												√	1
INDIVIDUAL TREE PLANTING													
Check stakes & ties; replace loose, broken, or decayed items to original specification. Adjust, refix or replace loose or defective ties, allowing for growth and to prevent chafing. - Where chafing has occurred, reposition, or replace ties to prevent further chafing											√		10
NATIVE MIXED HEDGING													
Maintain at 1.5m with slight batter to top, trim any rangy branches to 60cm width Cut each side on alternate years (each side to be cut once every 2 years)												√	1
WILDFLOWER/GRASSES SEEDING													
One cut per year in late September, remove arisings off site											√		1
LITTER PICKING													
	√	√	√	√	√	√	√	√	√	√	√	√	10

P01 26.10.23 Drawing Created AKW GS
Rev Date Information DR CH

IronsideFarrar
EnvironmentalConsultants
111 McDonald Road, EDINBURGH, EH7 4NW
0131 550 6500 | mail@ironsidefarrar.com

Project:
Lamination Line, Barony Road Facility, Auchinleck
Client:
Egger Barony Ltd.

Title:
Landscape Input - Maintenance Schedule

Scale: **1:2000** Paper Size: **A1**
Status:

Drawing Number: **64066-005** Revision: **P01**