



- KEY:**
- EXISTING SHRUBS**
  - NEW NATIVE WOODLAND PLANTING TO SCHEDULE**
  - WILDFLOWER PLANTING**  
SCOTTISH LOWLAND MEADOW MIX BY SCOTIA SEEDS OR APPROVED EQUIVALENT @ 4g/m<sup>2</sup>
  - POND PLANTING TO SCHEDULE**
  - MIXED NATIVE HEDGE**

WILDLIFE ENHANCEMENTS TO REFLECT RECOMMENDATIONS OF BEP. LOCATIONS OF ELEMENTS IS INDICATIVE ONLY AND IS RECOMMENDED AS BEING LOCATED ON SITE BY ECOLOGIST

- BEE HOTEL (nr. 1)**
- DEADWOOD PILES (nr. 3)**
- WOODCRATE BAT BOXES (nr. 2)**  
SCHWEGLER OR APPROVED EQUIVALENT
- WOODCRATE BIRD BOXES (nr. 5)**  
BY SCHWEGLER

| Native Woodland Planting              |                |         |             |                      |       |          |
|---------------------------------------|----------------|---------|-------------|----------------------|-------|----------|
| Name                                  | Root condition | Form    | Height (cm) | Habitat / min breaks | % Mix | Total no |
| <b>20% - Feathers (2m Centers)</b>    |                |         |             |                      |       |          |
| <i>Alnus Glutinosa</i>                | RB             | Feather | 175-250     | 5                    | 15    | 575      |
| <i>Pinus sylvestris</i>               | RB             | Feather | 125-150     | 2                    | 2.5   | 96       |
| <i>Prunus avium</i>                   | RB             | Feather | 125-150     | 2                    | 2.5   | 96       |
| Name                                  | Root condition | Form    | Height (cm) | Planting density     | % Mix | Total no |
| <b>60% - Transplants (2m Centers)</b> |                |         |             |                      |       |          |
| <i>Quercus robur</i>                  | BR             | 1 + 2   | 60 - 80     | 1 per m <sup>2</sup> | 20    | 767      |
| <i>Betula pendula</i>                 | BR             | 1 + 1   | 40 - 60     | 1 per m <sup>2</sup> | 30    | 1150     |
| <i>Alnus Glutinosa</i>                | BR             | 1 + 1   | 40 - 60     | 1 per m <sup>2</sup> | 10    | 383      |
| <b>20% Understorey (1.5m Centers)</b> |                |         |             |                      |       |          |
| <i>Sambucus nigra</i>                 | BR             | 1 + 1   | 80-100      | 1 per m <sup>2</sup> | 10    | 682      |
| <i>Corylus avellana</i>               | C              | 3L      | 40-60       | 1 per m <sup>2</sup> | 7.5   | 511      |
| <i>Crataegus monogyna</i>             | BR             | 1 + 1   | 80-100      | 1 per m <sup>2</sup> | 2.5   | 170      |

| Native Rural Hedgerow Planting |                |       |             |                  |       |          |
|--------------------------------|----------------|-------|-------------|------------------|-------|----------|
| Name                           | Root condition | Form  | Height (cm) | Planting density | % Mix | Total no |
| <i>Crataegus monogyna</i>      | BR             | 1 + 1 | 80 - 100    | 7 per 1 m        | 30    | 833      |
| <i>Rosa canina</i>             | BR             | 1 + 1 | 60 - 80     | 7 per 1 m        | 20    | 555      |
| <i>Sambucus nigra</i>          | BR             | 1 + 1 | 80 - 100    | 7 per 1 m        | 20    | 555      |
| <i>Prunus spinosa</i>          | BR             | 1 + 1 | 60 - 80     | 7 per 1 m        | 15    | 416      |
| <i>Corylus avellana</i>        | BR             | 1 + 2 | 60 - 80     | 7 per 1 m        | 15    | 416      |

| Pond Planting               |          |                      |       |          |
|-----------------------------|----------|----------------------|-------|----------|
| Name                        | Pot size | Planting density     | % Mix | Total no |
| <i>Agrostis Stolonifera</i> | 2Lt      | 7 per m <sup>2</sup> | 65    | 4368     |
| <i>Glyceria Species</i>     | 2Lt      | 7 per m <sup>2</sup> | 35    | 2352     |

|     |          |                 |     |    |
|-----|----------|-----------------|-----|----|
| P01 | 25.10.23 | Drawing Created | AKW | GS |
| Rev | Date     | Information     | DR  | CH |

**IronsideFarrar**  
EnvironmentalConsultants  
111 McDonald Road, EDINBURGH, EH7 4NW  
0131 550 6500 | mail@ironsidefarrar.com

Project:  
**Lamination Line, Barony Road Facility, Auchinleck**  
Client:  
**Egger Barony Ltd.**

Title:  
**Landscape Input - Landscape Plan**

Scale: **1:1250** Paper Size: **A1**  
Status:

Drawing Number: **64066-002** Revision: **P01**