



599120mE
268800mN

599120mE
268780mN

599120mE
268760mN

- GENERAL**
- DO NOT SCALE THIS DRAWING. ALL DIMENSIONS ARE IN METRES UNLESS OTHERWISE NOTED. ANY DISCREPANCIES ARE TO BE RECORDED AND REPORTED TO THE ENGINEERS IMMEDIATELY.
 - THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL OTHER ENGINEERS AND ARCHITECTS DRAWINGS AND THE SPECIFICATION.
 - ANY EXISTING DETAILS WHICH ARE SHOWN ON THIS DRAWING ARE FOR GUIDANCE ONLY AND ARE TO BE CHECKED ON SITE BY THE CONTRACTOR. ANY VARIATIONS ARE TO BE RECORDED AND REPORTED TO THE ENGINEER IMMEDIATELY.
 - ALL WORK ARE TO BE TO THE SATISFACTION OF THE ENGINEER AND LOCAL AUTHORITY BUILDING CONTROL.
 - THE CONTRACTOR IS RESPONSIBLE FOR AND MUST TAKE ALL NECESSARY PRECAUTIONS TO ENSURE THE STABILITY OF THE WORKS AT ALL TIMES DURING CONSTRUCTION.
 - ALL WORKMANSHIP AND MATERIALS ARE TO BE TO CURRENT BRITISH STANDARDS.
 - ALL SERVICES ARE TO BE LOCATED AND PROTECTED AS NECESSARY BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF THE WORKS.
 - ALL HIGHWAY WORKS ARE TO BE IN ACCORDANCE WITH THE LOCAL AUTHORITIES DESIGN GUIDE AND SPECIFICATION.
 - PRIOR TO THE OCCUPATION OF THE FIRST DWELLING, STREET NAMEPLATES SHALL BE ERECTED IN ACCORDANCE WITH THE HIGHWAY AUTHORITY AND TO THE WORDING AGREED WITH THE PLANNING AUTHORITY.
 - DURING CONSTRUCTION WORKS ON SITE, ALL ROADS AND FOOTPATHS ARE TO BE SWEEPED AND KEPT CLEAR OF OBSTRUCTIONS, THIS IS TO INCLUDE EXISTING HIGHWAYS AS APPROPRIATE TO ENSURE SAFE PASSAGE OF ALL ROAD USERS.
 - PROVISION SHALL BE MADE FOR THE INSTALLATION OF ALL MAINS SERVICES INCLUDING DUCTING PRIOR TO THE LAYING OF THE ROAD BASE-COURSE.
 - ALL ADAPTABLE SURFACE WATER SEWERS WITHIN ADAPTABLE HIGHWAYS ARE TO BE A MINIMUM OF 225MM.
 - ALL WATER AUTHORITY SEWER WORKS ARE TO BE IN ACCORDANCE WITH "SEWERAGE SECTOR GUIDANCE APPENDIX C" DESIGN AND CONSTRUCTION GUIDANCE VERSION 1.0 25TH OCTOBER 2019 AND ANY ADDENDUM THEREAFTER.
 - ALL PRIVATE CONNECTIONS TO ADAPTABLE SEWERS SHOULD BE A MINIMUM OF 100mm DIAMETER (FOUL) & 150mm DIAMETER (SURFACE) MADE IN VITRIFIED CLAY CONNECTING SOFFIT TO SOFFIT.
 - NO TREES ARE TO BE PLANTED WITHIN 3M OF ANY ADAPTABLE SEWER AND TREE PITS/ROOT BARRIER ARE TO BE USED WHERE TREES ARE WITHIN 3-6M AS SPECIFIED BY THE WATER AUTHORITY.

KERB LAYOUT KEY

EDGING KERB (EF)	
HALF-BATTERED KERB 100mm UPSTAND	
BULL NOSE KERB (BN2) 25mm UPSTAND	
BULL NOSE KERB (BN2) 0mm UPSTAND	
DROPPER KERB	
DISH CHANNEL KERB	
SPEED TABLE/ SHARED SURFACE RAMP	
TACTILE PAVING	

REFER TO ENGINEERING LAYOUTS DRAWING NOS.
070 & 071 FOR PRIVATE DRIVE SPOT LEVELS.

Rev	Revision Notes	Drawn	App'd	Date

INGENT
CONSULTING ENGINEERS
Unit 10 Brightwell Barns, Waldringfield Road, Brightwell, Suffolk, IP10 0BJ.
Tel: 01473 598038 --- www.ingent.co.uk --- email: info@ingent.co.uk

PRELIMINARY

Project:
**RICHER ROAD, BADWELL ASH
SUFFOLK**

Drawing Title:
**ROAD SETTING OUT
SHEET 1 OF 3**

Client: BG & JM SUTTON	Date: SEPT 2023
--------------------------------------	---------------------------

Drawn: JH	Designed: JH	Checked: DCH	Approved: RGW
---------------------	------------------------	------------------------	-------------------------

Scale:

Project No: 2005-453	Drawing No & Revision: 010	Size: A1
--------------------------------	--------------------------------------	--------------------

